

# Innovation Funding Incentive Annual Report

Issue 1 – 31<sup>st</sup> July 2012

IFI Projects April 11 – March 12

For SP Distribution Ltd, SP Manweb plc and SP Transmission Ltd



### **Foreword**

SP Energy Networks (SPEN) welcomes the increasing importance Ofgem has placed on innovation through both the new RIIO (Revenue = Incentives + Innovation + Output) TI and ED1 business regulation models for transmission and distribution networks commencing 1st April 2013 and 2015 respectively.

During the reporting year 2011/12, we realised our ambition of maintaining a balanced portfolio of forty IFI projects that embraced the range of Technology Readiness Levels from concept through to trial and demonstration, which are presented in this annual report.



Once again we have acheived significant leverage of R&D spend through collaboration and, alongside these projects, we have progressed Low Carbon Network Funded (LCNF) projects at both Tier 1 and 2 level. For all projects we will maintain our focus to ensure early adoption and commercialisation, as appropriate.

SPEN has continued its strategic deployment of wide ranging IFI projects including new and existing projects with academic and industrial partners. Of particular note are two separate projects aimed at accurately measuring fault level from network disturbances and the management of fault level through the development and trial of a Super Conducting Fault Current Limiter. If both prove successful they will enable DNOs to improve network security without exceeding fault level rating of switchgear and enable optimisation of switchgear replacement programmes.

Keenly awaited is the opening of the world-class Power Networks Demonstration Centre (PNDC) at Cumbernauld, adjacent to SPEN's existing training centre. This is a project that SPEN has been actively championing for a number of years in recognition of the need to test and demonstrate new technologies in a controlled and safe environment under a range of operating scenarios prior to their deployment on the Distribution network. We anticipate this facility will be completed by the end of 2012.

In addition we are delighted to have become a major partner in the Technology and Innovation Centre which represents the cornerstone of the University of Strathclyde's single-biggest investment in its research capacity. The industry-led research aims to accelerate the pace of research and development, attracting new jobs and inward investment and will provide graduates with the necessary knowledge to meet our industry needs.

In a rapidly changing energy sector we continue to scan the technology horizon for innovation and invest in appropriate research and development activities that will help to realise the low carbon vision for the benefit of all.

Frank Mitchell CEO, SP Energy Networks



## **Contents**

FOR	REWORD	2
1.	INTRODUCTION & BACKGROUND	5
1.1	Context	5
1.2	Innovation Funding Incentive (IFI)	5
2.	SP ENERGY NETWORKS STRUCTURE	é
3.	OVERVIEW	7
3.1	IFI Overview	7
4.	SUMMARY TABLES	8
5.	ACHIEVEMENTS FOR 2011/12	9
5.1	Development of Partnerships	g
5.2	Power Networks Demonstration Centre	g
6.	HIGHLIGHTS FROM 11/12	11
6.1	Prototype Low Voltage Jumpers with Integral Circuit Breaker	11
6.2	EPRI - High Voltage Direct Current Programme Engagement	12
6.3	Vegetation Management	13
6.4	Remote Engineering Access To Pole Mounted Auto Reclosers	14
6.5	Outram Fault Level Monitor	16
APP	PENDIX A – EXPENDITURE BREAKDOWN OF PROJECTS BETWEEN LICENCES	18
	Summary Table Notes	
	Cost Breakdown	
	Programme Management Costs	
	Project Progress Curves	
APP	PENDIX B – PROJECT REPORTS IFI PROJECTS	22
	IFI 0401 STP 2 Overhead Lines	
	IFI 0401 STP 3 Cable Networks	
	IFI 0401 STP 4 Substations	
	IFI 0401 STP 5 Networks for Distributed Energy Resources	
	IFI 0404 - Alternative Insulating Oils – Phase 1IFI 0409 - LV Fault Location Devices	
	IFI 0507 - Sensor Networks (Smart Dust) – Phase 2	
	IFI 0509 - Superconducting Fault Current Limiter	
	IFI 0511 - Voltage Control ACTIV (EATL)	
	IFI 0515 - Power Network Demonstration Centre (PNDC)	



IFI 0526 - PD Monitoring of Cables (11 & 33kV)	36
IFI 0607 - LV Network Automation	38
IFI 0615 - ScottishPower Advanced Research Centre (SPARC)	40
IFI 0618 - Supergen 1 – FlexNet	44
IFI 0621-2 LV Sure	46
IFI 0621-3 Live Alert – Energised Alert	48
IFI 0621- 4 PURL2	_
IFI 0625 - Vegetation Management - ADAS	51
IFI 0701 - ENA IFI Projects	
IFI 0711 - 3 <sup>rd</sup> Party ROEP Risk Assessment	
IFI 0712 - BT 21 <sup>st</sup> Century Protection Solutions (BT21CN)	57
IFI 0713 - Wide Area Monitoring, Protection & Control (WAMPAC) for GB and IRL	59
IFI 0801 - IEC 61850 Application in SP - Transmission	
IFI 1001 – Offline Planning Tool for Dynamic Thermal Rating	
IFI 1002 - Supergen HiDEF	65
IFI 1003 - Strategic Asset Lifecycle Value Optimisation "SALVO"	67
IFI 1004 - Remote Access to Pole Mounted Auto Reclosers	69
IFI 1005 - GIS Impedence Mapping - zMap	71
IFI 1007 – Outram Fault Level Monitor	
IFI 1101 – EPRI	74
IFI 1102 – Energy Storage Project	76
IFI 1103 – PD Monitoring in Supergrid Transformers	
IFI 1107 –Cable Identification Devices	79
IFI 1108 –ESRI Powerfactory	
IFI 1201 –Lynx Kelvatek LV Switch	81
IFI 1202 – Nanodielectrics	82
IFI 1203 – Psymetrix ACAM Phase 1	83
IFI 1204 – LV Jumpers with Integral CB	84
IFI 1209 - Substation Earth Integrity Monitoring System	85
IFI 1210 –Transmission SSR & Harmonics	86



## 1. Introduction & Background

### 1.1 Context

Ofgem introduced the Innovation Funding Incentive (IFI) as a mechanism to promote and encourage network related Research & Development (R&D). The primary aim of the incentive is to encourage the electricity network operators to apply innovation in the way they pursue the technical development of their networks.

Ofgem recognised that innovation has a different risk/reward balance compared with a network operators' core business. The incentive provided by the IFI mechanism is designed to create a risk/reward balance that is consistent with research, development and innovation. The two main business drivers for providing this incentive at this time are the growing need to efficiently manage the renewal of network assets and to provide connections for an increasing capacity of renewable generation at all voltage levels. These are significant challenges that will both benefit from innovation.

### 1.2 Innovation Funding Incentive (IFI)

The IFI is intended to provide funding for projects focused on the technical development of distribution and transmission networks, to deliver value (i.e. financial, supply quality, environmental, safety) to end consumers. IFI projects can embrace any aspect of the distribution / transmission system asset management from design through to construction, commissioning, operation, maintenance and decommissioning. The detail of the DNO IFI mechanism is set out in the Special Licence Condition C3, Standard Licence Condition 51 (for the Distribution Licences), the Electricity Transmission Licensees' IFI mechanism is set out in the special licence condition J5 Part 3 or special licence condition D5 part 2, and standard licence condition B16 Part C.

With the extension of IFI to the transmission licences, agreement at the ENA R&D Working Group was given to the creation of a common Good Practice Guide (GPG) considering IFI for electricity distribution, transmission and gas transmission networks; Version 2 of Engineering Recommendation G85 issued in December 07.



### 2. SP Energy Networks Structure

SP Energy Networks (SPEN) is the part of ScottishPower UK Ltd, which owns and operates the electricity transmission and distribution network of southern Scotland and the electricity distribution network of Merseyside and North Wales. Day-to-day operation of our network, approaching 112,000 km, is conducted by SP Energy Networks, a wholly owned subsidiary of ScottishPower Ltd. Since April 2007 ScottishPower has been part of the Iberdrola Group.

Our transmission and distribution licence assets come under three wholly owned subsidiaries:

- SP Distribution: The electricity network of 33kV and below in southern Scotland
- SP Manweb: The electricity network of 132kV and below in Merseyside and North Wales
- SP Transmission: The electricity network of 132kV and above in southern Scotland

IFI activity is co-ordinated centrally on behalf of these licences, this report relates to R&D activity undertaken on:

- SP Distribution Ltd, referred to as SP-D in this report
- SP Manweb plc, referred to as SP-M in this report
- SP Transmission Ltd, referred to as SP-T in this report




Figure 1: UK Map showing the territory of (a) SP Distribution & SP Transmission and (b) SP Manweb



### 3. Overview

### 3.1 IFI Overview

A total of 40 IFI projects are being reported by SP Energy Networks on behalf of the three ScottishPower Network licence areas for the period  $1^{st}$  April  $11 - 31^{st}$  March 12.

At time of writing SPEN has a total of c.£5.5m authorised IFI projects, representing a levered portfolio of over £35m. The projects cover a breadth of R&D providers from academia, to consultants, to manufacturers with projects ranging in investment from £4k to £250k IFI input, and development timescales of between 6 months and 4 years.

Our R&D activity has increased significantly since the introduction of the IFI. We have continued to focus on leveraging our programme through collaboration with funding bodies, other network operators or external suppliers / manufacturers. In 2011/12 every £1 of SP IFI money invested in a project was levered by c.£5 from other sources:

R&D growth in SPEN (SP-D, SP-M and SP-T) since the introduction of the IFI									
	Expenditure	No. Of	Yearly						
SP-D, SP-M and SP-T	(Internal +	Reported	Programme						
	External)	Projects	Leverage						
2004/05 (Early Start)	£223k	12	c. £1.5m						
2005/06	£546k	36	c. £3m						
2006/07	£1,282k	41	c. £5m						
2007/08	£1,793k	50	c. £7m						
2008/09	£1,978k	38	c. £9m						
2009/10	£1,462k	35	c. £7m						
2010/11	£1,621k	27	c. £8m						
2011/12	£1,975k	40	c. £11m						




Figure 2 IFI Spend



## 4. Summary Tables

The following tables have been adapted from the Regulatory Instructions and Guidance documents (RIGs).

IFI Summary - SP Distribution Ltd Licence Area 11/12	
SP Distribution Ltd Network Revenue	£346,000,000
IFI Allowance	£1,730,000
Unused IFI Carry Forward to 2011/12	£968,400
Number of Active IFI Projects	28
Summary of benefits anticipated from IFI projects 2011/12	1
External expenditure [2011/12] on IFI projects	£680,674
Internal expenditure [2011/12] on IFI projects	£218,955
Total expenditure [2011/12] on IFI projects	£899,629

IFI Summary - SP Manweb plc Licence Area 11/12	
SP Manweb plc Distribution Network Revenue	£301,270,000
IFI Allowance	£1,506,350
Unused IFI Carry Forward to 2011/12	£646,600
Number of Active IFI Projects	33
Summary of benefits anticipated from IFI projects 2011/12	1
External expenditure [2011/12] on IFI projects	£453,777
Internal expenditure [2011/12] on IFI projects	£196,937
Total expenditure [2011/12] on IFI projects	£650,714

IFI Summary - SP Transmission Ltd Licence Area 11/12	
SP Transmission Ltd Distribution Network Revenue	£207,380,000
IFI Allowance	£1,036,900
Unused IFI Carry Forward to 2011/12	£501,200
Number of Active IFI Projects	14
Summary of benefits anticipated from IFI projects 2011/12	<u> 1</u>
External expenditure [2011/12] on IFI projects	£349,281
Internal expenditure [2011/12] on IFI projects	£75,658
Total expenditure [2011/12] on IFI projects	£424,939

Further detail on these tables is provided in Appendix A of this report.

\_

 $<sup>^{\</sup>rm 1}$  Summary of benefits are available in Section 6 "Highlights from 11/12"



## 5. Achievements for 2011/12

At the end of 2011/12 the highlights from the SPEN IFI portfolio included:

- Every IFI project undertaken by SP is taken before a panel of senior experts from across the business. Through this process we have:
  - 40 live projects
  - o 11 new projects were authorised during the 2011/12
  - Of the 40 projects, 7 are now complete and either awaiting adoption or formal closure
- Over £11m of leverage obtained

### 5.1 Development of Partnerships

The current programme consists of the following collaborative projects:

- EPSRC 2x industry roles in Supergen programmes: Supergen 1 Flexnet; HiDef.
- DNO specific 25 collaborative projects with some / all UK DNOs via EA Technology, ENA or through direct collaboration (see Appendix B for details).
- Direct university partnership 1x ScottishPower Advanced Research Centre (SPARC) with the University of Strathclyde.
- Capenhurst Energy Innovation Centre A non-profit trust that over sees the management of the centre in collaboration with ScottishPower, Electricity North West, CE Electric, Scottish & Southern Energy and the North West Development Agency.
- Entering into our 3<sup>rd</sup> year of participation in the Electrical Power and Research Institute which has been strategically positioned to engage with our western link HVDC project.

### 5.2 Power Networks Demonstration Centre

This project initially proposed and led by SPEN, was to develop the first of its kind, in the UK, a full scale 11kV and LV prototyping network as a test-bed for active network management techniques and other 'high risk' technologies.

Whilst not a technological development in itself, this project is a fundamental enabler of technology, with significant potential to accelerate adoption of significant / radical developments across a range of IFI projects. The centre can be used to investigate the impact of intermittent generation and penetration of EV technologies on the LV network as well as testing of new tools and training.

Since late 2008, SPEN have been working with collaborative partners (University of Strathclyde, Scottish & Southern Energy and Scottish Enterprise) to develop the design.

The building of the Centre commenced in 2011 and handover of the facility to the University of Strathclyde will occur in November 2012. The University will then finish equipment installation with the aim of officially opening the building for business early January 2013.





Figure 3 Artists Impression of the Demonstration Facility



Figure 4 Construction Progress March 2012



## 6. Highlights from 11/12

Whilst not all benefits have a direct monitory value, we have indicated the benefits brought to SPEN in improvements to customer service, reductions to capital cost of equipment and the reduction in energy usage/carbon emissions.

# **6.1 Prototype Low Voltage Jumpers with Integral Circuit**Breaker

When work is undertaken on Low Voltage (LV) busbars it often necessitates that an outage is taken on the whole LV board and in most circumstances this will result in an outage for the customers supplied by the circuits off the board. In these circumstances the DNO will energise as many of the LV circuits as possible via either a mobile generator or a back feed from an LV interconnected substation. Unfortunately these solutions are not always feasible and some circuits will have to remain denergised during the work even when adjacent circuits are energised as shown opposite in Figure 5.




Figure 5 LV Board with Fuse removed




Figure 6 LV Board Feeding Radial Circuit

This project is looking to develop a safe and simple solution that will reduce the number of outages and requirement for mobile generators in the aforementioned scenario.

Based on a technical specification drawn up by operational field staff SPEN have developed a prototype LV Jumper that will safely energise an LV circuit by linking it to the spill of an adjacent circuit that is energised by a back feed, as shown in Figure 6.

The prototype includes an integrated 200A 3-phase LV circuit breaker enclosed in a ruggedized housing and utilises industry standard connectors that will enable the device to be connected securely and in a short space of time.

Over the next 6-12 months SPEN working alongside the manufacturer Ten47 expect to further

refine the design of the LV Jumper (shown in Figure 7) and carry out the necessary safety tests. This will be followed by live tests of the jumper in a controlled environment enabling guidelines for its usage to be drawn up. Assuming this goes

to plan the project will be extended to include the

Figure 7 LV Jumper Applied



widespread testing of several units in real outage scenarios.

### 6.2 EPRI - High Voltage Direct Current Programme Engagement



The power industry is faced with the difficulty of acquiring rights-of-way for new transmission lines, the need to improve the reliability of the power grid, and the challenges of integrating renewable power sources into power networks. High voltage direct current (HVDC) and flexible ac transmission system (FACTS) technologies offer some effective schemes to meet these demands.

SPEN is currently engaged in two significant HVDC deployments, the Western and Eastern Links. The Western Link, which is by far the most progressed, will link Scotland and Wales with a 2GW HVDC interconnector. The northern converter station will be located at Hunterston, adjacent to EDF Energy's nuclear site, with the southern convertor station planned for Deeside. The options for an Eastern Link are currently being developed by SPEN in conjunction with Scottish Hydro Electric Transmission Ltd (SHETL) and National Grid Electricity Transmission (NGET). This link will be around 2GW and will further increase the transfer capability between Scotland and England.

With this increasing focus on HVDC technology SPEN has been able to benefit from the research work undertaken by the Electric Power Research Institute (EPRI) in this area.

HVDC connections perform differently to ac connections during steady-state, dynamic, and transient conditions, and EPRI has a project studying these differences. This project will consider the coordination between HVDC links and ac lines in parallel for the most effective utilisation of these assets. System planning studies will be performed as a first step before considering HVDC interconnections in the existing ac grid to assess the impacts of HVDC. There is a growing need for systematic evaluation of the impacts of HVDC on the ac grid using the HVDC models for the latest convertor technologies. This project will address the HVDC impact evaluation studies using benchmark test systems and the necessary model developments. The project is coordinated with a supplemental project on the same topic in which application studies are conducted for the Great Britain Network for National Grid and Scottish Power.

Given EPRI's global reach and extensive research programme SPEN has been able to significantly leverage its research investment.

EPRI's current year HVDC and FACTS activities include:

- Providing a technology watch newsletter with the latest developments in HVDC and FACTS technologies
- Updating the leading reference guide for the design and operation of HVDC systems
- Resolving operational concerns of owners and operators of existing HVDC and FACTS systems, and those considering the addition of HVDC or FACTS to their systems
- Evaluating HVDC system performance and conduct component testing
- Evaluating HVDC electrical effects such as electromagnetic interference, fields, and corona in laboratory test settings




- Developing conversion of ac lines to dc lines to increase transfer capability on existing transmission corridors, including hybrid solutions where ac and dc lines share corridors or structures
- Developing schemes for power flow management using FACTS
- Demonstrating HVDC and FACTS technology options at utility sites

### **6.3 Vegetation Management**

Effective vegetation management is a critical component in assuring a safe and reliable electricity supply and represents a significant maintenance requirement and associated budget spend. Long term analysis of networks faults shows a significantly increasing trend in vegetation related faults in the UK electrical network. Given this trend a four year project was set up to gain an improved understanding of utility space (US) degradation, that is the physical volume occupied by overhead lines and additional space required to ensure safe and reliable operation.

ScottishPower along with other utility companies engaged in a vegetation management project with the aim of gaining an improved understanding of vegetation growth, in the UK, and in particular the closure of the safety space around electrical equipment over time. As part of this project meteorological record covering the UK for the past 40 years were analysed to create a complete set of bioclimatic zone maps for the UK. A network of approximately 1300 sites participated in the study and US closure in the spring and autumn of 2008, 2009 and 2010 was measured at all sites and a substantial database created that describes the spatial variation of vegetation growth across the UK during this period.

From the analysis of the results a national annual average change in US was determined. There was considerable variation by electrical distribution company and therefore by geographic region. In broad terms the project found that sites located in the warmer areas of southern England, experienced the average highest rates of growth with the lowest observed at relatively cooler Scottish Power Scotland sites.






Future climate predictions from the United Kingdom Climate Impacts Programme (UKCIP, 2009) were combined with US observations to predict future growth rates in the period 2020-2080 for a variety of climate impact scenarios. Results indicate a substantial change in bioclimatic zones in the UK for all UKCIP scenarios. It was predicted that the high vegetation growth rates associated with rapid US degradation that were observed in the warmer southern areas of England, including the south coast, parts of Cornwall and Devon will extend much further north and may reach as far as the North Midlands within the next decade or so. This indicates that climate change could have a substantial impact on the cost of vegetation management over the next 10 years if current levels of safety and reliability are to be maintained in a period of increasing growth rates.

A utility company has a duty to maintain safe clearances from overhead lines and the findings from this project can be used to help shape future vegetation management practices including the frequency and depth of cut used in maintenance regimes.

### 6.4 Remote Engineering Access To Pole Mounted Auto Reclosers

SPEN has a population of Noja pole mounted auto reclosers (PMAR) that are monitored and controlled via their SCADA system using a radio system. Limitations within the SCADA system mean that only a small number of data points can be monitored and controlled on the Recloser controller.

SPEN is working with Nortech to implement a system using GPRS that allows much more data to be returned from the Noja units. This data will provide further information about both ScottishPower's network and the Noja units themselves.




The Noja device incorporates a protection module which can be accessed to retrieve active and historical data relating to both protection activity and statistical metering.



This can only be accessed via an RS232 port within the Noja Control Panel that is mounted below the Main Tank, out with the Safety Distance, and above the Anti-climber. Consequently, there are several benefits that can be gained from this project including:

- The Health and Safety benefit of not having to climb the pole to access PMAR information;
- Ability to record short time interruptions (<1min);</li>
- Current and voltage values could be taken from the Noja during a fault event and incorporated into impedance maps for speedier fault locations; and
- Negating the need to visit each PMAR twice a year with subsequent OPEX savings.

Remote access via iHost will provide a dashboard screen showing key performance figures for the population of Noja PMAR.



Event logs from all PMARs will be collected automatically, removing the need to drive to site, so that there are no delays in getting data. There will be central storage of event logs and a summary analysis of PMAR activity with the dashboard showing a league table of operations.



### 6.5 Outram Fault Level Monitor

If the fault current passing through any network ever exceeds its designed fault level there is a possibility that the switchgear will fail disruptively. This is highly undesirable, at best the failure will necessitate the switchgear is replaced which will likely result in prolonged customer outages, however, of even greater concern is the potential for the failure to impact upon the health and safety of persons within the proximity of the substation.

Because of these reasons it is vital that DNOs ensure the network fault level is not exceeded. At present this is done using established connection rules and more often through network modelling packages such as IPSA and DigSILENT. These fairly complex models are built by experienced engineers and can take several days to build, however, despite their complexity every model will have some assumed parameters, particularly regarding the fault level contribution customers have. Whilst this approach will continue to serve DNOs well, due to the expected challenges faced by the network in the future it would be prudent to have an alternative method, particularly one that would complement existing models.

Through existing relations with Outram Research Ltd, SPEN discussed the possibility of developing an existing power quality instrument to measure / calculate fault level from naturally occurring network disturbances. These discussions lead to the demonstration of a single phase low voltage device that proved the feasibility of the approach. Subsequently SPEN and Outram have spent the last 18 months developing a portable Fault Level Monitor (FLM) that is applicable to every network voltage.



To date SPEN have deployed six FLMs on

the network and through the analysis of the results obtained the FLM firmware has been revised several times. The results obtained are also extremely encouraging as they in the range expected and consistently within 5-10% of the fault level result produced by the network model.

The remaining stage of the project will concentrate on the revision of the final version of the FLMs firmware, the development of its user interface and the production of support literature. It is also hoped that a suitable test facility can be identified to complete definitive tests on the FLM against a known fault level.

FLMs have two immediate uses to DNOs:

- To validate and refine existing system analytical models by obtaining visibility of actual system fault levels and contributions from customer equipment under a wide range of real-world scenarios
- The identification of the fault level in areas of network where network modelling may be difficult or problematic, e.g. sections of the 11kV or Low Voltage network.

The potential benefits associated with the above are as follows:



- The **Health and Safety** benefits of identifying and subsequently managing fault level issues which were previously unknown due to inaccurate or non-existent models.
- Operational benefits that are gained from the ability for optimal operation or interconnection of the network which could be restricted due to a perceived fault level issue.
- **Financial** rewards associated with an improved Regulatory Performance rectifying fault level issues, e.g. removal of perceived fault level issues by accurate monitoring as opposed to conventional equipment-based solutions.
- New Connection the benefits associated with facilitating new network connections
  which previously may have been problematic or financially prohibitive due to modelling,
  scenario and data inaccuracies.
- **Environmental** benefits associated with the connection of renewable generation as detailed above and the moth-balling of equipment ahead of its end of life due to fault level upgrades.





Appendix A – Expenditure Breakdown of Projects between Licences



### **Summary Table Notes**

During the collation of the 05/06 report we revised our methodology for NPV assessments for IFI projects. It is noted that the figures described in the tables should be interpreted with caution, as the figures quoted in the NPVs will only be realised upon completion of the project, and once fully adopted into the business.

### Cost Breakdown

As SP Energy Networks operate distribution and transmission licenses for the SP-D, SP-M and SP-T areas, successful developments relating to distribution and/or transmission assets undertaken in one part of the business will equally apply to the other. In line with this, costs have been split against each licence based on the turnover and hence size of each network area.

Cost Breakdown between Licence Areas										
Licence Area	Annual Turnover (11/12)	Percentage Split Distribution	Percentage Split Transmission							
SP-Distribution	£346.00 million	~60%	NA							
SP-Manweb	£301.27 million	~40%	~15%							
SP-Transmission	£207.38 million	NA	~85%							

Projects identified as only applying to one licence, or ones that apply in favour of one, two or all three licences have been scaled accordingly (See Table A1). This is defined when the project inception document is developed.

### **Programme Management Costs**

Internal costs for projects detailed in Appendix B are based on SP's input to a project through meetings, correspondence, trials, etc scaled by the appropriate hourly rate for an individual's grade.

### Net Present Value (NPV) source

It is noted that IFI projects address a range of issues, and the benefits achieved, and those accounted for in the NPV can be categorised into the following areas:

- Avoided cost A successful development may negate the need to spend money on network components. As an example the development of a high capacity circuit, would avoid the need for duplicate traditional circuits for a given network application.
- Direct savings Successful development could result in a direct financial benefit, e.g. through reductions in operating costs, reduced exposure to Regulatory penalties, etc.
- Managing risk A successful development would assist in reducing the risk profile of the company, either through greater understanding of causes / effects of actions on, or as a result of, network operation (equipment failure, etc.)
- Strategic These projects impact on the longevity of the network, either through external influences such as changes in load / generation patterns, the impact of climate change or even skills / resources.

NB. Whilst an NPV calculation if possible for any project, and across any of these areas, it is recognised that as the assessment looks further to the future (as is the case for strategic projects), the benefits are more susceptible to risk, more uncertain, and consequently less robust.



As of 31<sup>st</sup> March 2012 the status of the 40 projects reported as well as those that have stopped is detailed below.

IFI Proj	ject Status		
No.	Phase	Definition	External Cost
6	Proposals in development	Agreeing scope / objectives, setting up contracts, etc.	None Direct (small external £ associated with management cost)
27	Live projects	Live projects Projects in progress	
2	Completed projects	Projects which have completed their trial phase	Yes

This breakdown accounts for reasons why not all projects have significant external spend.

### **Project Progress Curves**

Expenditure profiles are described below to give an appreciation of costs that will be required prior to a project realising a stated benefit through the development cycle. Figure A1 shows a hypothetical expenditure profile for a development project. Expenditure is defined as:

- External Money paid to 3<sup>rd</sup> parties for work (consultancy, purchase of equipment, monitoring, etc)
- Internal SP Energy Networks' staff time on eligible IFI development work
  multiplied by the appropriate hourly rate. The success of a project is highly
  dependent on the levels of internal support a project is given.
- Overall investment The total cost of a project (predominantly external cost) of which the company is accessing through collaborative or external funding leverage. This is the combined investment from SP Energy Networks and other collaborative partners.

In line with sound project management, all IFI projects have been staged into milestones, i.e. the R&D provider will only receive payment upon successful completion of a defined stage.




Figure A1: Example Expenditure Profile for an IFI Project



## Table A1 is ordered chronologically.

Project Description		Percentage split			£split SPD SPM SPT										
		SPM	SPT	E	xternal	-	nternal	E	xternal		nternal	E	xternal	_	ternal
IFI 0401 - Strategic Tech Prog	55%	35%	10%	-	111,158	£	34,371	£	70,737	£	21,872	£	20,211	£	6,249
IFI 0404 Alternative Insulating Oil Project	60%	40%	0%	£	14,111	£	6,848	£	9,408	£	4,565	£	-	£	-
IFI 0409 - LV Fault Location devices	60%	40%	0%	£	7,311	£	8,445	£	4,874	£	5,630	£	-	£	-
IFI 0507 Sensor Networks - Smart Dust	60%	40%	0%	£	9,111	£	7,449	£	6,074	£	4,966	£	-	£	-
IFI 0509 - Superconducting Fault Current Limiter	60%	40%	0%	£	38,420	£	12,694	£	25,613	£	8,463	£	-	£	-
IFI 0511 - ACTIV Voltage Control	0%	100%	0%	£	-	£	-	£	996	£	13,410	£	-	£	-
IFI 0515 - Power Network Demo Centre	60%	40%	0%	£	198,516	£	6,157	£	132,344	£	4,105	£	-	£	-
IFI 0526 - PD MONITORING	60%	40%	0%	£	37,164	£	4,451	£	24,776	£	2,967	£	-	£	-
IFI 0607 LV Network Automation	60%	40%	0%	£	111	£	13,359	£	74	£	8,906	£	-	£	-
IFI 0615 - SP Advanced Research Centre	30%	20%	50%	£	56,709	£	3,032	£	37,806	£	2,022	£	94,514	£	5,054
IFI 0618 - Supergen 1 - Flex Net	60%	40%	0%	£	12,111	£	5,558	£	8,074	£	3,705	£	-	£	-
IFI 0621-2 LV Sure	60%	40%	0%	£	7,533	£	4,451	£	5,022	£	2,967	£	-	£	-
IFI 0621-3 Live Alert	55%	35%	10%	£	102	£	4,080	£	65	£	2,597	£	19	£	742
IFI 0621-4 PURL2	60%	40%	0%	£	85,311	£	5,497	£	56,874	£	3,665	£	-	£	-
IFI 0625 - Vegetation Management Project	55%	35%	10%	£	3,766	£	6,524	£	2,397	£	4,152	£	685	£	1,186
IFI 0701 ENA Small Value Projects	55%	35%	10%	£	4,211	£	4,080	£	2,680	£	2,597	£	766	£	742
IFI 0711 - 3rd Party ROEP Risk Assessment	30%	20%	50%	£	56	£	2,765	£	37	£	1,844	£	93	£	4,609
IFI 0712 - BT21 CN Solutions	60%	40%	0%	£	15,783	£	8,645	£	10,522	£	5,763	£	-	£	-
IFI 0713 - WAMPAC	0%	0%	100%	£	-	£	-	£	-	£	-	£	62,339	£	7,419
IFI 0801 - IEC 61850 Applications in SPT	0%	0%	100%	£	-	£	-	£	-	£	-	£	36,863	£	8,750
IFI 1001 - DTR DURHAM	0%	20%	80%	£	-	£	-	£	2,037	£	3,508	£	8,148	£	14,031
IFI 1002 - SUPERGEN HIDEF	60%	40%	0%	£	3,111	£	8,445	£	2,074	£	5,630	£	-	£	-
IFI 1003 - SALVO	55%	35%	10%	£	102	£	5,179	£	65	£	3,295	£	19	£	942
IFI 1004 - Remote Access to Pole Mounted Auto Reclosers	60%	40%	0%	£	22,263	£	8,927	£	14,842	£	5,951	£	-	£	-
IFI 1005 - zMap - GIS Imp	60%	40%	0%	£	21,026	£	8,445	£	14,017	£	5,630	£	-	£	-
IFI 1007 - Outram Fault Level Monitor	60%	40%	0%	£	2,798	£	17,232	£	1,865	£	11,488	£	-	£	-
IFI 1101 - EPRI	30%	20%	50%	£	29,379	£	3,440	£	19,586	£	2,293	£	48,965	£	5,733
IFI 1102 - Energy Storage Project	60%	40%	0%	£	111	£	8,563	£	74	£	5,709	£	-	£	-
IFI 1103 - PD Monitoring in Supergrid Transformers	0%	0%	100%	£	-	£	-	£	-	£	-	£	76,421	£	8,750
IFI 1107 - Cable Identification Devices	60%	40%	0%	£	111	£	5,822	£	74	£	3,881	£	-	£	-
IFI 1108 - ESRI Powerfactory	60%	40%	0%	£	111	£	5,293	£	74	£	3,529	£	-	£	-
IFI 1201 - Lynx Kelvatek LV Switch	0%	100%	0%	£	-	£	-	£	186	£	8,750	£	-	£	-
IFI 1202 - Nanodielectrics	0%	100%	0%	£	-	£	-	£	186	£	8,750	£	-	£	-
IFI 1203 - Psymetrix ACAM Phase 1	0%	100%	0%	£	-	£	-	£	186	£	17,327	£	-	£	-
IFI 1204 - LV Jumpers with integral CB	60%	40%	0%	£	111	£	6,605	£	74	£	4,403	£	-	£	-
IFI 1209 - Substation Earth Integrity Monitoring System	35%	35%	30%	£	65	£	2,597	£	65	£	2,597	£	56	£	2,226
IFI 1210 - Transmission SSR & Harmonics	0%	0%	100%	£	-	£	-	£	-	£	-	£	186	£	9,226

	SF	D	SP	M	S	T
Totals	External	Internal	External	Internal	External	Internal
	£ 680,674	£ 218,955	£ 453,777	£ 196,937	£ 349,281	75657.7635
Ratios	76%	24%	70%	30%	82%	18%

Table A1: Overview of 11/12 projects showing application between licences



## Appendix B – Project Reports IFI Projects April 11 – March 12



Project Title	IFI 0401 STP 2 Overhead Lines								
Description of project	A DNO research a	and develo	pment col	laboration ho	sted by E.	A Technology			
Expenditure for 11/12 financial year	External £50	5,623 ),526 5,149	Expenditu previous ( financial y	(IFI)	Internal External Total	,			
Project Cost (Collaborative + external + [DNO])	£288,650		Projected costs	Projected 12/13 costs		£10,000 £50,000 £60,000			
Technological area and / or issue addressed by project									
Type(s) of innovation	Incremental	Project B Ratii			sidual Risk	Overall Project Score			
involved	incremental	:	16	9	ı	25			
Expected Benefits of Project	If successful pro	-		ıle may incı	rease the	performance and			
Expected Timescale to adoption	Range 1-5 y dependent on			ation of bene nce achieved		Range 3-5 years - ependent on project			
Probability of Success	Range 49-95% - on proje	=	Bene <sup>-</sup>	ject NPV = (P fits – PV Cost ability of Succ	s) x	£42,652			
Potential for achieving expected benefits	Collectively, the 11/12 work programme demonstrates the developm innovative products, processes and techniques that improve the manag of overhead lines. A full list of projects and deliverables are available from or EA Technology					ve the management			
Project Progress to March 12	Only a small number of projects or project stages started in the Module during 11/12 have been completed since the majority are multi-stage projects that span more than one year								
Collaborative Partners	Other DNOs								
R&D Providers	EA Technology								



Project Title	IFI 0401 STP 3 Ca	IFI 0401 STP 3 Cable Networks							
Description of project	A DNO research a	and develo	pment col	laboration ho	sted by E	A Technology			
Expenditure for 11/12 financial year	External £50	5,623 ),526 5,149	Expenditu previous ( financial y	(IFI)	Internal External Total	£45,915 £342,042 £387,957			
Project Cost (Collaborative + external + [DNO])	£748,550	Projected 12/13   Internal £10,000   External £60,000   Total £70,000							
Technological area and / or issue addressed by project	operational performance, an	The Module 3 programme for budget year 2011/12 aimed to improve operational performance, maximise potential benefits, improve financial performance, and minimise risk associated with cable networks. A full list of projects and deliverables are available from SPEN or EA Technology							
Type(s) of innovation	Incremental	Project Benefits Rating Project Residual Risk							
involved	incremental	:	14	8	1	22			
Expected Benefits of Project	If successful pro	-		ıle may inci	rease the	performance and			
Expected Timescale to adoption	Range 1-2 y dependent on			ation of bene nce achieved		Range 3-5 years - pendent on project			
Probability of Success	Range 45-100% - on proje	=	Bene	ject NPV = (P fits – PV Cost ability of Succ	s) x	£42,013			
Potential for achieving expected benefits	innovative produ	cts, proce ks. A full	sses and t	echniques th	at improv	ne development of the the management are available from			
Project Progress to March 12	11/12 have beer	Only a small number of projects or project stages started in the Module during 11/12 have been completed since the majority are multi-stage projects that span more than one year							
Collaborative Partners	Other DNOs								
R&D Providers	EA Technology								



Project Title	IFI 0401 STP 4 Su	bstations						
Description of project	A DNO research a	and develo	opment col	laboration ho	sted by EA	Technology		
Expenditure for 11/12 financial year	External £50	5,623 0,526 5,149	Expenditu previous ( financial y	(IFI)	Internal External Total	£43,396 £255,512 £298,908		
Project Cost (Collaborative + external + [DNO])	£243,061	Projected 12/13   Internal £10,000   External £40,000   Total £50,000						
Technological area and / or issue addressed by project	The Module 4 programme for budget year 2011/12 aimed to improve operational performance, maximise potential benefits, improve financial performance, and minimise risk associated with substations. A full list of projects and deliverables are available from SPEN or EA Technology							
Type(s) of innovation	Incremental	Project Benefits Rating Project Residua				Overall Project Score		
involved	meremental	1	6.5	9.	5	26.0		
Expected Benefits of Project	If successful pro	-	this Modu	ıle may incı	rease the	performance and		
Expected Timescale to adoption	Range 1-4 y dependent or			ation of bene nce achieved		ange 1-6 years - pendent on project		
Probability of Success	Range 30-95% - on proje	-	Bene Bene	ject NPV = (P fits – PV Cost ability of Succ	s) x	£32,721		
Potential for achieving expected benefits	innovative produ	Collectively, the 11/12 work programme demonstrates the development of innovative products, processes and techniques that improve the management of substations. A full list of projects and deliverables are available from SPEN or EA Technology						
Project Progress to March 12	-	n complet				the Module during tage projects that		
Collaborative Partners	Other DNOs							
R&D Providers	EA Technology							



Project Title	IFI 0401 STP 5 Net	IFI 0401 STP 5 Networks for Distributed Energy Resources							
Description of project	A DNO research a	nd develo	pment col	aboration ho	sted by I	EA Technology			
Expenditure for 11/12 financial year		,623 ,526 ,149	Expenditu previous ( financial y	(IFI)	Interna Externa Total	,			
Project Cost (Collaborative + external + [DNO])	£276,875	Projected 12/13   Internal £10,000   External £50,000   Total £60,000							
Technological area and / or issue addressed by project	operational performance, and	The Module 5 programme for budget year 2011/12 aimed to improve operational performance, maximise potential benefits, improve financial performance, and minimise risk associated with networks for distributed energy resources. A full list of projects and deliverables are available from SPEN or EA Technology							
Type(s) of innovation	Incremental	Project Benefits Rating Project Residual Risk Sc							
involved	incremental	13.5 8.			5	22.0			
Expected Benefits of Project	If successful pro	-	this Modu	ıle may incı	rease th	e performance and			
Expected Timescale to adoption	Range 1-3 ye dependent on			ation of bene nce achieved		Range 2-5 years - lependent on project			
Probability of Success	Range 51-100% - on projec	=	Bene <sup>r</sup>	ject NPV = (P fits – PV Cost ability of Succ	s) x	£28,841			
Potential for achieving expected benefits	innovative produc	cts, proces distribute	sses and to ed energy	echniques th resources.	at impro A full I	the development of ove the management list of projects and			
Project Progress to March 12	Only a small number of projects or project stages started in the Module during 11/12 have been completed since the majority are multi-stage projects that span more than one year								
Collaborative Partners	Other DNOs								
R&D Providers	EA Technology		-						



Project Title	IFI 0404 - Alternative In	sulat	ing Oil	s – Pha	ise 1						
Description of project	Applied research progra a thorough evaluation in both aged power trai	of the	e electi	rical/ag	geing p	ropert	-		_		
Expenditure for financial year	Internal £11,413 External £23,519		Expe previ	nditure ous (IF	in		Internal External <b>Total</b>		£	£19,995 £77,668	
Project Cost (Collaborative + external + SPEN)	Total £34,932 £142,290		Proje for SI	cted 12	2/13 c	osts	Inter Exter	nal nal	-		
Technological area and / or issue addressed by project	the relative merits for I	Evaluation of the Characteristics of Alternative Fluids is being undertaken to access the relative merits for Retro-Filling Power Transformers and filling New Transformers with alternative fluids have over using standard mineral oils.									
Type(s) of innovation	Incremental	S	Signific	ant		echnolo substitu	-		Ra	ıdical	
involved	No	No No Yes No									
Expected Benefits of Project	<ul><li>Potential to up-rate</li><li>Opportunity to implement</li></ul>	Potential to up-rate transformers at strategic sites.									
Expected Timescale to adoption	4 years	4 years  Duration of benefit once achieved 20 years									
Probability of Success	50%		1	2 2	RL De	velopm 4	nent (S <sup>.</sup>	tart – (	Current 7	8	9
Project NPV	(Present Benefits x Pro Costs	babili	ty of S	uccess)	– Pres	sent			£98,92	2	
Project Progress March 12	The output of the project indicates that differences in electrical strength between ester liquids and mineral oil are clearly shown in non-uniform electric fields. The observation that the lightning impulse and AC strengths of ester liquids are comparable with the mineral oil in a quasi-uniform field certainly moves the application of ester liquids in large power transformers a step forward. It implies that the designed operation electric stresses and therefore the basic size and configuration of an ester-filled transformer can be similar to that of a mineral oil filled unit.  Nevertheless, additional considerations should be given to ester-filled power transformers. First, since streamers in the ester liquids, once incepted, propagate faster and further, the avoidance of streamer/discharge inception is more important for design and construction of an ester-filled power transformer so as to avoid breakdown, particularly under the factory test stresses; second, to compensate for the lower breakdown strength of the ester liquids in a large divergent field gap, additional pressboard barriers (in a direction perpendicular to the field) may be required to partition large oil gaps in an ester-filled power transformer.										
Potential for achieving expected benefits	30 journal and conference papers have been published out of the research project 'Applications of Alternative Oils in Large Power Transformers'.  This project has given confidence in the deployment of ester based oils. SPEN has used Midel in 33kV transformers and the work undertaken in this project has reinforced SPEN's understanding that alternative fluids can be used in large power transformers, as long as it is considered at the design stage due to the difference in										
Collaborative Partners		clearance, insulation and cooling requirements.  National Grid, EDF Energy, Areva T&D, TJH2B, M&I Materials, EPSRC, TJH2B									
R&D Provider	University of Manchest	er									



Project Title	IFI 0409 - LV Fault	Location D	evices									
Description of project	A device for use o and correlate to an		_			captu	re trar	sient	fault ir	nforma	ation	
Expenditure for financial year	External £ 12	4,075 2,186 <b>6,261</b>	Expenditure in previous (IFI) financial years				Ex	ternal ternal o <b>tal</b>	f	E53,72 E101,4 E <b>155,1</b>	139	
Project Cost (Collaborative + external + SP-EN)	£184,800	Projec SP-EN	ted 1	12/13 co	osts for	Ex	ternal ternal o <b>tal</b>	f	0 0 <b>EO</b>			
Technological area and / or issue addressed by project	The device is bein location.	the device is being developed preliminary for transient/intermittent LV cable faul ocation.									fault	
Type(s) of innovation	Incremental	Incremental Significant				ological tution			Radio	cal		
involved	Yes	No			N	0			No			
Expected Benefits of Project	<ul><li>Reduce the nu</li><li>Minimise the r</li></ul>	<ul> <li>Minimise the number of joint holes</li> <li>Remove the fault from the system in a shorter timescale than traditional 'cut-and-</li> </ul>										
Expected Timescale to adoption	1 Year		Durati achiev		f benefi	t once	de	Typically 8-10 years depending on technology development				
Duchahilitus af			TRL Development					art – Cı	urrent)		<b>T</b>	
Probability of Success	50%		1	2	3	4	5	6	7	8	9	
Project NPV	(Present Benefits x	Probability	of Succ	ess)	– Prese	nt Costs		:	£349,2	40	<u> </u>	
Project Progress March 12	The final stage of the project has now been completed with the units being rolled out into the business											
Potential for achieving expected benefits	This project has no	This project has now closed										
Collaborative Partners	Uk PowerNetworks	Uk PowerNetworks, Electricity North West										
R&D Providers	Kehui (UK) Ltd, Noi	rtech										



Project Title	IFI 0507 - Sensor Net	works (S	mart D	ust) –	Phase	2						
Description of project	self-configuring wire information in a serie relayed through a gastudy into the use of 11kV overhead line not be following on from the	'Smartdust" is a concept developed by the University of California that is based on a self-configuring wireless sensor network, capable of transmitting low bandwidth information in a series of short hops. Data acquired and transmitted from sensors is relayed through a gateway for data interpretation. ScottishPower led a feasibility study into the use of this technology for detecting the passage of fault currents on L1kV overhead line networks.  Following on from this work, a collaborative project has been scoped between EDF-Energy, Central Networks and SPEN to develop a product based on this principle for										
	the remote signalling				-	-						
Expenditure for financial year	Internal £12,415 External £15,186	(II		penditure in previous I) financial years			Inter	nal	£1	77,907 192,098	8	
Project Cost	Total £27,600						Inter			<b>270,00!</b> 15,000		
(Collaborative +	Phase 1 = £16k Phase 2 = £191k		rojecteo PEN	12/1	3 costs	s for	Exter			19,000		
external + SPEN)	A cheap and reliab	lo ::-:	t	ocii-	+16.5	ot t-	Total			34,000		
Technological area and / or issue addressed by project	penalties. This technology would be especially suited to transitory fault location.  Significant analysis has been undertaken on the deployment characteristics of GSM/GPRS Fault Passage Indicators Vs Radio communicating sensors, using SP-D fault histories. The analysis considering the relationship between sensor cost, deployment penetration and improvement to CML figures. The key conclusion is that a cheap, low power semi-mesh radio based system:  • Allows a much higher percentage of locations of be monitored economically than any other option, across all price points and time savings  • Offers SP a much higher NPV than any other option  Owing to these factors, a significantly higher percentage of network can be monitored (from 10% for GSM devices to above 70% coverage for radio sensors), increasing the likelihood that they will be targeting faults (rather than solely focussing on worst performing circuits).							fault ment o, low ically tored g the				
Type(s) of innovation	Incremental	S	ignifica	nt			nologi stitutio			Radica	al	
involved	No		No				No			Yes		
Expected Benefits of Project	Sensor Networks implemented as a method of fault passage indication (FPI) could have an enormous effect on how faults on the overhead network are located. They could have a huge impact on CI/CML figures as the technology would be effectively pin pointing faults on the network. This results in a significant financial saving											
Expected Timescale to adoption	5 Years			tion of achiev	bene <sup>†</sup> ved	fit		1	0 Year	S		
							oment (Start – Current)					
Probability of Success	50%		1	2	3	4	5	6	7	8	9	
			<u> </u>		<u> </u>						L	



Project NPV	(Present Benefits x Probability of Success) – Present Costs £554.5k						
Project Progress March 12	Progress in 2011/2012: Phase B has now started and final adjustments are being made to the devices to enable the construction of field ready trial devices.  There have been some technical difficulties adapting the prototype lab part of the project into a device that can be trialled on the DNO's networks. This will hopefully be rectified Q3 of 2012 to enable a field trial early 2013.						
Potential for achieving expected benefits	This new approach will allow control engineer's to identify the location of a fault more quickly than is presently possible and hence rapidly deduce the best supply restoration strategy. It will also allow linesmen to be sent directly to the source of the fault to identify and fix the problem. Whilst the overall effect should be a reduction in Customer-Minutes-Lost for permanent faults, it will more importantly be able to capture the source of transient fault activity that can cause multiple supply interruptions. In the longer term, this system can become duplex, allowing control commands to be sent to specific wFPI locations.						
Collaborative Partners	Central Networks						
R&D Providers	Willow, E.ON Power Technology						



Project Title	IFI 0509 - Supercon	ducting l	Fault C	urrent	Limite	r					
Description of project	This project aims Current Limiting (SF							Supercoi	nduc	ting	Fault
Expenditure for financial year	Internal         £21,1           External         £64,0           Total         £85,1	)33	-	diture nancia	-		Inter Exter <b>Total</b>	nal	£3	1,699 88,69 <b>30,3</b> 9	93
Project Cost (Collaborative + external + SPEN)	£2,345,967		Projec SPEN	cted 12	/13 co	sts for	Inter Exter <b>Total</b>	nal	£1	,000 2,000 8,000	
Technological area and / or issue addressed by project	when the material resistance, thereby increased current (liquid nitrogen) careverts to a normal Being a solid state after which the immeans (protection sufficiently fast to subsequent limited Three devices (one applications: transf	The development of a non-linear 'high-temperature' superconducting ceramic series with a circuit breaker for the clamping and clearance of fault energy.  When the material is operated at below its critical temperature it loses all electric resistance, thereby allowing load current to flow with negligible losses. Either thincreased current density caused by fault current, or the loss of cooling mediu (liquid nitrogen) causes the temperature of the superconducting material to rise and reverts to a normal resistive state.  Being a solid state device, the SFCL has been proven to operate in a few millisecond after which the impedance remains high until the fault is cleared by convention means (protection operated circuit breakers, fuses, etc.). The SFCL's operation sufficiently fast to ensure that the first peak of the fault current is limited. The subsequent limited current can be set to suit a specific application.  Three devices (one per DNO) will be constructed and installed covering a range applications: transformer tails, bus section, interconnected network connection. The successful completion of this project is likely to pave the way for higher voltage.								trical r the dium and it  onds, ional on is The	
Type(s) of innovation involved	Incremental No	Si	gnifica Yes	nt		Fechnolog substitut No	_		Rad N		
Expected Benefits of Project	To develop, unders 11kV fault current l Successful trials wil are capable of clam will open up anoth	To develop, understand and address the issues associated with the connection of an 11kV fault current limiting device to the network.  Successful trials will result in the development of commercially available devices that are capable of clamping fault levels to within network design limits. Once proven, this will open up another option for tackling network fault level, potentially providing an alternative to network reinforcement.									
Expected Timescale to Adoption	3 years		Dura achie	tion of ved	benef	it once		20	years	5	
Probability of Success	25%		1	2	RL De	velopmei 4		t – Curre		8	9
Project NPV	f-267,191  (Present Benefits x Probability of Success) – Project NPV is negative due to low TRL / high costs upon commencement							the			



Project Progress March 12	Work has now been carried out at Ainsworth Lane to install the FCL. The energisation date is now going to be August 2012
Potential for achieving expected benefits	Learning from this project will be able to help SPEN make strategic decisions on the future of fault level management
Collaborative Partners	Electricity North West, CE Electric UK, Applied Superconductor Ltd
R&D Providers	Applied Superconductor Ltd



Project Title	IFI 0511 - Voltage Con	trol AC	TIV (EA	TL)							
Description of project	network and facilitate it is to undertake field	his project is to investigate active voltage control to increase the efficiency of the etwork and facilitate the connection of distributed generation. More specifically is to undertake field trials of the Fundamentals SuperTAPP n+ automatic voltage ontrol (AVC) relay and develop associated modelling criteria for network planners.									
Expenditure for financial year	Internal	-	enditur financi	-			rnal ernal	£	40,069 97,944 1 <b>38,01</b>		
Project Cost (Collaborative + external + SPEN)	£254,206	-	Projected 12/13 costs for SPEN Internal £0 External £0 Total £0								
Technological area and / or issue addressed by project	1	t is proposed that this relay could provide a viable alternative for voltage control cross SP-M / SP-D in areas where the ratios of generation to load is high.									
Type(s) of innovation involved	Incremental	Incremental Significant Technological Radical									
involved	Yes	Yes No No No									
Expected Benefits of Project	which requires mi Improving the vol Reducing the reincreasing the cap Reducing the risk equipment and in	tage proquirements for the contraction of volting pring prin	ofile of ent for or the co age bei personn	supply netwonnecting out	; ork ext ion of d side sta	ensior istribu	ted ge	eneratio	n; and		
Expected Timescale to adoption	<2 Years	Durat achie	ion of l	penefit	once			10 Yea	irs		
			1		velopm		art –		1	ı	
Probability of Success	75%	1	2	3	4	5	6	7	8	9	
Project NPV	(Present Benefits x Pro Costs	l obabilit	y of Su	ccess) -	– Preser	nt	£67,4	145			
Project Progress March 12	This project has now c	This project has now closed									
Potential for achieving expected benefits	This project has now closed										
Collaborative Partners	Central Networks, Sco	ttish &	Southe	rn Ene	rgy, Elec	ctricity	North	n West			
	EATL, Fundamentals										



Project Title	IFI 0515 - Power Ne	twork De	emonstration	Centre (PNI	DC)				
Description of project	Development of a figround for active no Whilst not a technology, with developments acros	full scale etwork m blogical d significa	11kV and LV anagement to evelopment in the potential to the second secon	prototyping echniques and n itself, this to accelerate	network and other 'hand project is	nigh risk' a fundan	technologies. nental enabler		
Expenditure for financial year	Internal £10, External £330		Expenditure previous (IF years	e in	Internal External <b>Total</b>		£44,189 £99,659 <b>£143,848</b>		
Project Cost (Collaborative + external + SPEN)	£7,200,000		Projected 1 for SPEN	2/13 costs	Internal External <b>Total</b>		£20,000 £250,000 <b>£225,000</b>		
Technological area and / or issue addressed by project	<ul> <li>In partnership with collaborators, this project aims to:</li> <li>Provide a demonstration network to allow the testing of new technologies or 'real' network</li> <li>Offer a real network that will incorporate 11kV and low voltage equipmer containing real loads, real generation and test real technologies</li> <li>Create a facility which will be open to Academia, R&amp;D Establishmen Manufacturers, and Network Operators</li> <li>The vision is to create a physical scale model that can represent different urba suburban and rural electrical networks. The proposed system will incorporate renetwork components: cables, overhead lines, switchgear, transformers, protecti and control equipment, in order to ensure it is both representative and credible to to real thing. Real Time Digital Simulators (RTDSs) will be used in parallel to model underlying, more comprehensive network, effectively expanding the scale of the system.</li> <li>Technologies coming more prominently into play over the next 15 years, e.g. microgeneration, storage, fault current limiters, etc., will be included on the test network as to test their effect, and vice-versa, on both marine and distribution systems.</li> </ul>								
Type(s) of innovation involved	Incremental	Sig	nificant		ological itution		Radical		
IIIVOIVEU	Yes		Yes	Y	es		Yes		
Expected Benefits of Project	Safety – A test net operation of a mor run through repeat to train pilots. Risk mitigation – A and microGen will i manage the increas Acceleration of tria network through a	Benefits to DNOs from such a facility include:  Safety – A test network with dedicated staff will offer a facility to train staff in the operation of a more complicated network. Specific what-if scenario courses can be run through repeatable simulation, in the same manner as flight simulators are used to train pilots.  Risk mitigation – A real time simulator, with likely penetrations of high volume DG and microGen will indicate the technologies that will need to be developed in order to manage the increased risk this might pose to the network and/or our customers.  Acceleration of trials / increased adoption rate – The ability to operate the whole network through a vast range of loading conditions in a short period of time, will lead to the end of long duration (12-24mth) network trials of new technologies.							
Expected Timescale to adoption	1 Years		Duration of benefit 20 Years						
Probability of Success	25%		1 2	RL Developn	1 1	6 7	nt) 8 9		
Project NPV	(Present Benefits x	(Present Benefits x Probability of Success) – Present Costs £709,171							



Project Progress March 12	<ul> <li>Activity Apr 2011 - March 2012</li> <li>The main building is completed. Work on the network has commenced.</li> <li>Initial research Agenda completed, three projects are now underway.</li> <li>One Director has been appointed as well as one full-time research manager.</li> <li>Value proposition and growth plan has been proposed to the board.</li> <li>Timescales for completion</li> <li>Handover of the facility to the University will occur in November 2012. The University will then finish equipment installation with the aim of officially opening the building for business early January 2013.</li> </ul>
	Facility – Operation and SP role Overall governance will be carried run by the PNDC Directors, Operational and Research (UoS staff).  The Core Research Programme, will be planned and approved by the PNDC board which comprises of the PNDC directors, UoS finance director and Tier 1
Potential for achieving expected benefits	members.  There are three classes of membership: Founder Tier 1, Tier 1 and Tier 2, each having different voting rights on the PNDC board.
	For SPEN to get maximum value out of the PNDC we will be seeking to use our place on the PNDC board to our maximum advantage in guiding the PNDC core programme to benefit our IFI programme.
	We also anticipate that SPEN will have various projects that will require the use of the Centre to reduce their time to adoption within SP.
Collaborative Partners	Scottish & Southern Energy, Scottish Enterprise and University of Strathclyde
R&D Providers	See Collaborative Partners



Project Title	IFI 0526 - PD Monitoring of Cables (11 & 33kV)									
Description of project	<ul> <li>Partial discharge (PD) monitoring technology is a tool often used for identifying HV cable sections that are at risk of failing in the near future. There are two distinct methods of testing for PD:</li> <li>Long term monitoring to identify the degradation of the cable which signals the increase in risk of failure; and</li> <li>PD mapping which pinpoints the location of any discharge along the route of the cable.</li> <li>Developing the technology to apply these methods gives a network operator the evidence required to assist in targeting investment / cable replacement, with a net improvement in network performance.</li> <li>This project will develop a portable PD monitoring product that can be moved around the network, as tool in the prioritisation in cable replacement.</li> </ul>									
	Internal £7,419				•		Interna	al	£20,444	
Expenditure for financial year	External £61,94		Expenditure in previous (IFI) financial years		5	Extern	al	£72,232		
	Total <b>£69,35</b>	9	(,ae.a. yeare				Total		£92,676	
Project Cost		D.					Interna	al	£5,000	
(Collaborative + external + SPEN)	1 +160,000		rojected 12/13 costs for PEN			Or	Extern	al	£13,000	
external + 31 EW)							Total		£47,650	
Technological area and / or issue addressed by project	This project will devertested on the SP 11kV  To develop a suicable sections with the short term. minutes to many Following initial those cable sectundertaken.  Based on the PD identified as crit replaced. The call it is planned that the with results from the in the knowledge rule.	retwork table por nich are et The porta weeks. testing in maps obtained, will ble/joints et est resite testing can be testing the testing can be testing the testing can be testing the testing testing the testing testing the testing the testing testing the testing testing testing the testing testi	with the table monemitting a sable monemone of the table monemone of the table monemone of the table subjection of the table of t	follownitoring level itor when ary signistering are to rewill the collection of the	ring ail ing solu of disc ill allo ubstat ng the eas of eview hen be ated in her Ul chnoke	ms: others ow SP tions, e high conce and teste n a d CONC	with the e, which to the partial partial energy length of the entrate selected to value at a bas Ds, will	ne abi ch cou st for al disc vel of ed cab alidate e, whi allow	lity to idential lid lead to for a period of the harge map discharge, activity, where sections are PD test resich, in conjusted	tify any faults in f a few ping of will be will be will be sults.
Type(s) of innovation	Incremental	S	ignificant				ologica titution		Radio	cal
involved	No		Yes				No		No	)
Expected Benefits of Project	<ul> <li>Developing PD m to cable degrada aid justification a</li> <li>Anticipated key l savings through t</li> </ul>	tion will a nd priorit penefits v	assist with ising of ca vill be in	cable pital s the ar	e repla spend. ea of	ceme CML	ent dec	ision- impro	making. It v	will also
Expected Timescale to adoption	1-2 Years		Duratio once ac	hieve	d				5 Years	
Probability of Success	50%		TRL Development (Start – Current)  1 2 3 4 5 6 7 8							9



Project NPV	(Present Benefits x Probability of Success) – Present Costs	£108,661						
Project Progress March 12	Work is been carried out to analyse the top 20 worst performing circuits in SPM and SPD or faulted cable section so that a more targeted application of cable monitoring can be arried out.							
Potential for achieving expected benefits	Having correctly verified sources of PD in cable and ide of concern, the next stage is to monitor the top 20 n SPM and SPD.  If these cable sections are found to have high levels location of PD section, expose cable section and replace	nost problematic circuits in both s of PD it is planned to identify						
Collaborative Partners	N/A							
R&D Providers	HVPD (Formally IPEC HV)							



Project Title	IFI 0607 - LV Network	Automo	ition								
Description of project	The aim of a Low Voltage Automation (LVA) project is to provide a trial system on Scottish Power Energy Networks (SPEN's) LV network, which will prove the benefits of implementing a larger scale LVA system across the LV networks. The trial system will consist of one LVA CCU (modified old CCU) and one phase LVA switch.  It is two major parts that will be validated in the project. The first one is the communication from the control point to the LVA switch. The communication technique will be the Power Line Communication (PLC). The second part is the mechanical behaviour and the control of the Magnetic vacuum Switch from EPS.										
	Internal £22,265								£1	153,358	3
Expenditure for financial year	External £186	-	enditu ) financ	-		S	Exter	nal	£2	205,950	)
·	Total £22,451		,	•			Total		£3	359,308	3
Project Cost		D		12/12			Inter	nal	£1	15,000	
(Collaborative + external + SP-EN)	£257,775		jected EN	12/13	costs 1	or	Exter	nal	£9	95,000	
external + 3F-LIV)						Total		£1	10,000	)	
Technological area and / or issue addressed by project  Type(s) of innovation	network, providir installation on the	circuits.									
involved	No		Yes			No	)	No			
Expected Benefits of Project	Application of the technology should provide the following benefits:  Reduction of CMLs on the LV network Increased asset life of circuit elements by the reduction of both fault currents and stresses during fault location Reduced cost and time of fault location through rapid identification of faults location Elimination of repeated intermittent faults										
Expected Timescale to adoption	3 Years		Dura achie		benef	it once	!		10 Ye	ars	
Drobability of						/elopm					
Probability of Success	50%		1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Probability of Success) – Present £526,7k										



Project Progress March 12	Due to problems with the supplier Radius, this project has been delayed. Work has continued with the switching device through EPS.  A production run of 9 units have been manufactured and are awaiting installation on the network on a trial basis.
Potential for achieving expected benefits	Having proved the LVA could perform in this environment, coupled with the control and network behaviour data capability, we have now embarked on a continuation IFI project to further develop this prototype into a final product that will enable the Smart Grid concept.
Collaborative Partners	None
R&D Providers	RADIUS



Project Title	IFI 0615 - ScottishPower Advanced Research Centre (SPARC)											
Description of project	<ul> <li>Three workstreams have been proposed:</li> <li>Asset Engineering: Field based activities, concentrating on the technologies used to gather and interpret data then control and manage individual assets.</li> <li>Asset Strategy: Office, desktop, PC based analytical activities including the analysis of data, concentrating on underlying trends of asset populations (from asset ageing to network performance).</li> <li>System Development: Forward looking network design activities considering the connectivity between the assets. It should consider both the medium term (5 years) and longer-term trends (&gt;10 years), which will affect the design of the network (e.g. load, generation, standards, regulations, Ofgem incentives/penalties).</li> <li>A number of related projects will be developed within each workstream.</li> </ul>											
Expenditure for financial year		29,136  Expenditure in previous (IFI) financial years				Inter Exter <b>Tota</b>	nal	£30,683 £481,067 <b>£511,750</b>				
Project Cost (Collaborative + external + SP-EN)	<b>£460,083</b> Projected 12/13 of SP-EN			/13 costs for Exte		Exter	Internal £10,000 External £160,00 Total £170,00		00			
Technological area and / or issue addressed by project	<ul> <li>Asset Engineering research stream focuses on methods and technologies that enable better use of individual assets.</li> <li>Asset Strategy research stream focuses on methods and tools that enable better management of populations of assets.</li> <li>System Development research stream focuses on analytical techniques that provide SP with better capability to plan and design the power system.</li> </ul>											
Type(s) of innovation	Significant	Projec R	t Ben ating	efits	F	-	t Resid Risk	dual	C	Overall Project Score		
involved			18				1			:	L7	
Expected Benefits of Project	Research activities vincluding system per the SPARC proposal, programme of deliver	formance which are	, OPE	X and	CAP	EX. k	Key ar	eas h	ave be	een id	entifie	ed in
Expected Timescale to adoption	3 Years Duration once ach				achie	eved				10 Yea		
Probability of Success	Varies per pr	oject	1	TR 2	L Dev 3	elopm 4	ent (S	6	Curre	ent) 8	9	
Project NPV	(Present Benefits x Probability of Success) – Present Costs  TBC In development for the core projects in each workstream							ch				



# 'Investment Strategy' Theme: Automated analysis of SCADA data and digital fault records for analysis of power system protection performance

- Develop, implement and test a prototype Post-Fault Protection Performance Analysis Suite:
  - 1. The prototype is currently within the final testing stage with testing conducted on an ongoing basis. The storms of January 2012 have become the final case studies and the preliminary results produced by the prototype are currently available for validation.
  - 2. Updates carried out to web-front end to improve performance and carry out general view improvements.
  - 3. Writing and drafting of journal paper for submission in March/April 2012.

## 'Investment Strategy' Theme: Smart Power Network Asset Management Strategies and Tools

- Develop a method to optimise targeting of investment for asset replacement over a given period of time.
  - 1. Investigated existing approach to asset investment planning, including identification of constraints.
  - 2. Investigated Markov Chain asset deterioration modelling technique.
  - 3. Investigated optimization techniques for application to investment planning.
  - 4. Selected, applied and evaluated suitable optimisation technique to specified assets.
  - 5. Developed and tested 'proof of concept' application of selected optimisation approach for asset investment planning. This involves development of spreadsheet tools to test the 'proof of concept'.

#### 'System Development' Theme: Optimal Distribution Network Architectures

- Develop algorithm and tool for network reconfiguration for loss and reliability optimisation prototype:
  - 1. Produced a document detailing the reconfiguration arrangements output by the loss minimisation algorithm. This was sent to Geoff Murphy to obtain feedback from network planners on how closely this matches existing running arrangements and how practically feasible these switching arrangements would be to implement.
  - 2. Developed a software user interface by using QT. (QT is a open source guitool).
  - 3. Developed a report function which can generate a report of the optimization results.
  - 4. Developed reliability analysis function using FMEA method and optimised for CI and CML analysis.

#### Project Progress March 12



#### 'Asset Technology' Theme: PD Diagnostics in MV Cables

Develop firmware and hardware for double sided PD monitoring system and signal processing algorithms:

- Firmware developed for the double sided PD monitoring system previously developed has been improved to increase the accuracy of PD location and has been verified in laboratory tests. Also, additional circuitry was incorporated in the double-ended system to provide immunity to external interferences so that the system can be installed in harsh environments.
- EMD and SGWT based de-noising algorithms has been developed using novel
  thresholding methods. These algorithms were tested with analytical and onsite data. Accuracy of these methods has been compared with existing denoising methods in terms of PD magnitude and PD location accuracies and
  the results are encouraging.

#### Project Progress March 12

### Additional (non-PhD) research projects:

Anglesey PV Penetration Study:

- The study established a generic methodology for assessing threshold levels for PV generating capacity connecting to the LV network, indicating where voltage quality and phase imbalance issues become problematic for the LV network. The study involved:
  - 1. The development of a methodology for modelling the PV system and analysing the voltage profile along the feeder based on limited measuring data (phase connection, PV output, customer consumption).
  - 2. The development of a network case study to assess the voltage level along a feeder, using DIgSILENT *PowerFactory* software.
  - The development of an 'easy to use' voltage assessment tool in MS-Excel (based on a simplified model derived from the observations made from the more sophisticated network study).
  - A final report detailing the approach taken to the network modelling, simulations (including assumptions) and PV penetration assessment tool development.



Potential for achieving expected benefits	<ul> <li>The 'Automated analysis of SCADA data and digital fault records for analysis of power system protection performance' PhD project of the Investment Strategy theme is expected to deliver significant enhancements to the PEDA system developed from previous research conducted by the University of Strathclyde in collaboration with SPEN protection engineers. Following discussions with SPEN and Iberdrola, the focus of this work changed from that originally defined to ensure that the proposed system leverages the network and protection Scheme information now available from the newly developed 'Protection Database'. The use of accurate representations of network and scheme connectivity will significantly improve the reliability and accuracy of the protection assessment output delivered and offer valuable decision support to protection engineers.</li> <li>The 'Smart Power Network Asset Management Strategies and Tools' PhD project of the Investment Strategy theme will develop a methodology involving asset deterioration modelling and optimisation techniques to enable asset managers to establish desirable optima balancing of asset health, risk and investment, providing a more robust scientific basis for justifying asset investment. In addition to optimizing the level of investment required to manage risk satisfactorily, the methodology will also attempt to identify which assets provide the best return on investment, in terms of risk management.</li> <li>The 'Optimal Distribution Network Architectures' PhD project of the System Development theme is expected to deliver a method of minimising network losses by actively managing power flow through network reconfiguration within operational, planning and design timescales. The research will search for an optimal solution that respects multiple objectives, i.e. the need to minimise losses without compromising reliability, while respecting network constraints, e.g. fault levels. This will allow SPEN to implement operationally 'smarter' and more cost effective s</li></ul>
Collaborative	strategic objectives of SPEN.
Partners	N/A
R&D Providers	University of Strathclyde



Project Title	IFI 0618 - Supergen 1	IFI 0618 - Supergen 1 – FlexNet										
Description of project	preparing electricity programme of works. The programme reco through its integrati disciplines such as systems technology a	FlexNet is a four-year EPSRC funded programme that takes forward the process of preparing electricity networks for a low carbon future and builds on an initial programme of works, <b>FutureNet</b> that is nearing completion.  The programme recognises the interdependence of many factors in achieving change through its integration of the work of internationally recognised researchers from disciplines such as social psychology, economics, power systems analysis, power systems technology and public policy and the long-term, radical nature of the changes needed and is not dependant on any particular form of generation										
	Internal £9,26	3				In	Internal		£13,69	96		
Expenditure for financial year	External £20,18	86		nditure inancia			S	Ex	xterna	I	£73,51	L7
iniancial year	Total £29,4	48	(IFI) financial years			To	otal		£87,21	L <b>4</b>		
Project Cost								In	iterna		£0	
(Collaborative +	£7.4m		Proje SP-EN	cted 12	2/13 c	osts 1	for	Ex	xterna	I	£0	
external + SP-EN)		JF-LIN				To	otal		£0			
Technological area and / or issue addressed by project	design, public accept starting to showcase Government and Regular Some of the key issue How can we judge the How can flexibility be How much flexibility secondary plant givin What constrains or expenses.	achievements of <b>FutureNet</b> and lay out the major steps, technical, economic, market design, public acceptance and others, that will lead to flexible networks, including starting to showcase these so that they can be taken up by the commercial sector, Government and Regulators for practical implementation.  Some of the key issues to be addressed by the programme include: How can we judge the degree of flexibility needed? How can flexibility be achieved? How much flexibility should come from primary plant giving margin and how much from secondary plant giving enhanced controllability? What constrains or encourages flexibility, what technologies are acceptable and what economic frameworks and public policies provide flexibility at the least overall long-										
Type(s) of	Radical	Projec Rating	rt Benefits Project Residu Risk			lual	Overall Project Score			it .		
innovation involved		7.2			-2					9.2		
Expected Benefits of Project	Understanding of flexible network requirements able to cost-effectively deal with a wide range of possible futures  Develop networks that can 'think' for themselves  Engagement with stakeholders in progressing the research ideas toward deployment  Research that forms the basis of policy advice  Inputs to the UK government's Energy Review, the UKERC assessment of Intermittency, evidence to select committees of parliament and submissions to OFGEM consultations.											
Expected Timescale to adoption	2012 onwards		Dur	ation o	f bene hieved		nce	20	0 Year	S		
Probability of				1	1	evelo				Curren	<u> </u>	1
Success	25%		1	2	3	4	<u></u>	<u> </u>	6	7	8	9
Project NPV	(Dresent Benefits - Bresent Costs) v. Breshability of Costs											
Project NPV (Present Benefits – Present Costs) x Probability of Success £2M												



	The project has completed its 4 year programme (plus an extension period to close out
	The project has completed its 4-year programme (plus an extension period to close out a small number of the PhD projects). All work streams essentially completed their
	programme of work. As with any large R&D project, some task were modified in the
	light of results that emerged including the termination of unpromising avenues of
Project Progress	research and the refocusing onto others. Conclusions have been drawn in all areas and
March 12	the work written up for academic use and presented and demonstrated for research
	users. The training programme completed a series of discipline crossing training courses
	and industrial placements undertaken for researchers. The annual report to RCUK gives
	a more detailed account of progress and outcomes. Many outcomes are written up at
	www.supergen-networks.org.uk
	The breadth of FlexNet gives confidence that several of its activities will have enduring
Potential for	benefits. All the research partners have strong relationships with the DNOs/TSOs
achieving expected	through which to pursue the ideas to higher TRLs and make them part of the network
benefits	planning option set of the future. The ideas will also be pursued with
	equipment/software vendors and be subject of further research.
Collaborative	EPSRC, National Grid, Scottish and Southern Energy, Central Networks, EDF Energy
Partners	Networks, SP Energy Networks and CE Electric UK
	University of Bath, University of Birmingham, University of Cambridge, Cardiff
R&D Providers	University, University of Durham, University of Edinburgh, University of Exeter,
	University of Manchester, University of Strathclyde and Imperial College London.



Project Title	IFI 0621-2 LV Sure								
Description of project	<ul> <li>The development of LV Sure will take the SignalSure concept of circuit restoration and consider whether it could be applied to low voltage distribution networks. The project's objectives are to:         <ul> <li>Produce functional specification, detailed product development project plan &amp; test plan for the LVSure system</li> <li>Production of a prototype LVSure System and laboratory testing of the system</li> <li>Installation and testing of prototype on a representative test circuit</li> <li>Monitoring, evaluation and reporting of the performance of the trial system against functional specification</li> <li>Installation and demonstration of a number of prototypes on a selection of LV Networks</li> </ul> </li> </ul>								
Expenditure for financial year	Internal £7,4 External £12, Total £19,	556	Expenditure in previous (IFI) financial External £0 years Total £0						
Project Cost	£260,980	)	Projecto costs fo	ed 2012/13 or SPEN	£4,000 £26,380 £30,380				
Technological area and / or issue addressed by project	it has an incoming	lical isolating salong the LV of lited section a mated and done LV neong the route lit. Both the lince of a fault of mence the reore supply to voltage, then a closure. Circa restoration parents of a fault of literature in closure.	switches circuit.  Ind restores not rem.  Petwork to a sense on the estoration the estoration the first test down in the facuits with the facuits with the sense of the facuits with the sense of the first test down in the facuits with the sense of the facuits with the sense of t	oration of supply equire communicate IFU disconnection of supply equire communicate IFU disconnection voltage and authe ILU incorporate IEC in process by test as section. Each ILI wnstream and against an alternative section was the an alternative section and alternative section was the an alternative section.	ats supply attention between the sensing downstreating downstreating in turn value, if heals reached supply from	ted sections of the ween the devices  to the entire lly open, in effect g circuitry which m of each Unit. stream and if would initially sense lthy, restore when testing would m a remote end			
Type(s) of innovation involved	Tech Transfer Radical	Project Ber Rating 16		Project Residua	al Risk	Overall Project Score 17			
Expected Benefits of Project	<ul> <li>Successful completion of the project will result in:</li> <li>Knowledge of how to reconfigure and redesign LV networks to obtain optimum performance will be developed and transferred to the DNO.</li> <li>Avoid potential hazard of operator installing a replacement fuse of a live LV board with a faulted circuit.</li> <li>Assuming installation on worst performing (Rogue) LV circuits avoiding CML and CI associated with up to 5 transient interruptions per year per LV circuit would substantially and sustainably improve network performance for worst served customers.</li> <li>Reduction in potential risks from loss of traffic controls, street lighting, general lighting in public areas etc.</li> </ul>								



Expected Timescale to adoption	1 years	Duration of benefit once achieved	15 years					
Probability of Success	10%	Project NPV = (PV Benefits – PV Costs) x Probability of Success	£245,517					
Potential for achieving expected benefits	During the initial Stage 2 phase it was agreed that the project had delivered successful functional results but issues of thermal dissipation due to the use of power electronic switching components in a very small device envelope represented an additional design challenge.  An alternative operational technology has been identified which will allow the use of a much smaller contractor to switch off the residual current. If this technology is tested and is confirmed as being suitable for use on LV networks the next steps will be							
Project Progress to March 12	<ul> <li>to test the technology at high power laboratories and to develop a prototype.</li> <li>The initial prototype design and testing as outlined in Stage 2 was completed in June 2011</li> <li>An extension to Stage 2 (Stage 2a) was proposed. The proposal was to carry out a feasibility study to investigate if reducing the physical size of the power electronics device was possible, by applying alternative technologies.</li> <li>Stage 2a was completed successfully and has led to the next stage being about to start which is to design a fault current limiter based on the alternative operational technology which has already been identified as part of Stage 2a.</li> </ul>							
Collaborative Partners	Scottish Power, SSE, Surenet Te	echnology Ltd, Energy Innova	ition Centre					
R&D Providers	Surenet Technology Ltd							



Project Title	IFI 0621-3 Live Alei	rt – Energise	d Alert						
Description of project	<ul><li>voltages of above 2</li><li>To extend the v</li><li>To undertake a</li><li>To undertake fu</li></ul>	<ul> <li>To undertake a full market appraisal</li> <li>To undertake full evaluation of technology whilst in operation</li> </ul>							
Expenditure for financial year	Internal £7,4 External £186 Total £7,6	5	Expend previou years	iture in Is IFI financial	Interna Externa Total				
Project Cost (Collaborative + external + [DNO])	£ 65,815	;	Projected 12/13 costs for SPEN		Interna Externa Total				
Technological area and / or issue addressed by project	The Energised Alert senses any increase in electrical potential, above a predetermined threshold, of devices to which it is attached. Once triggered it is linked to an audible alarm, allowing the recognition and management of this potentially deadly hazard in a controlled manner. Its use will, therefore protect the operator, other employees and any members of the public in the vicinity from casual, but more importantly, avoidable electrocution.								
Type(s) of innovation	e.g. Incremental Tech	Project Be Ratin		i Project Resignal		Overall Project Score			
involved	<del>Transfer</del> Significant <del>Radical</del>	14				19			
Expected Benefits of Project	Successful development of the Energised Alert would:  Help prevent electrocution accidents and fatalities  Ensure 'live line' maintenance can be carried out in a safe manner  Allow operators to proactively respond to incidents on their network								
Expected Timescale to adoption	1 Year		Duratio	on of benefit once achieved	2	25 Years			
Probability of Success	75%		Bene	ject NPV = (PV fits – PV Costs) x ability of Success		£227,017			
Potential for achieving expected benefits	The project is on ta	arget to achie	eve the e	xpected benefits.	•				
Project Progress to March 12	<ul> <li>Stage One of the project, to design and develop the sensing system was completed successfully and met the deliverable set at the start of the project.</li> <li>Stage Two, to design and develop a refined was completed successfully and met the deliverable set at the start of the project.</li> <li>Stage Three, to manufacture and evaluate 10 energised alerts units is nearing completion. All units have now been manufactured however Stage Three can't be completed until the pilot sites for Stage Four have been agreed.</li> <li>The scope of Stage 4 is currently under review.</li> </ul>								
Collaborative Partners	Northern PowerGrid, Electricity North West, Scottish Power, SSE, Energy Innovation Centre, Live Alert								
R&D Providers	Live Alert								



Project Title	IFI 0621- 4 PURL2								
Description of project	EA Technology currently offers the PURL instrument to allow condition assessment of wooden poles and while the instrument performs this function well it is slow and complex to use and only makes use of a single measurement technique to make the assessment. Other instruments are currently available, however, these also base the estimate of pole strength on a single measured parameter; a few instruments use two (for example moisture content and fibre strength). A further major disadvantage with many of these instruments is that they physically damage the pole in order to make the measurement, therefore requiring ongoing maintenance e.g. annual Boron treatment.  PURL2 will make use of four measured parameters to increase measurement accuracy and reduce uncertainty. The techniques used for all measurements will have no more effect on the surface of the pole than standard climbing spikes so minimising ongoing maintenance requirements. All measurements will also be time and location stamped which, when combined with wired and wireless connectivity, will allow integration into field and office based asset management systems.								
Expenditure for financial year		62 2,186 1,347	_	iture in s (IFI) financial	Interna Externa Total	_			
Project Cost (Collaborative + external + SPEN)	£ 284,000	0	Project costs fo	ed 2012/13 or SPEN	Interna Externa Total	,			
Technological area and / or issue addressed by project	The new PURL will combine the existing ultrasonic attenuation measurement technique with measurements of ultrasonic time of flight, water content and surface hardness to provide a more accurate and reliable assessment over a wider range of degradation types and environmental conditions. More advanced coupling techniques would be used to speed up and simplify the measurement process compared to the current instrument.								
Type(s) of innovation	Significant	Project Be Ratin		Project Residua	al Risk	Overall Project Score			
involved		16		3		19			
Expected Benefits of Project	PURL 2 will represent a real advance on the current technology available and should result in more efficient, more accurate and less damaging condition assessment of wood poles. The benefits of this should be:  • Better use of inspection team resource • More effective identification of failing poles and therefore:- • Reduced failure of wood poles which will result in:- • Reduced CMIs/CLs, which in combination with the above will result in:- reduction in overall cost								
Expected Timescale to adoption	1 Year		Duration of benefit once achieved 10 Years						
Probability of Success	10%		Bene	ject NPV = (PV fits – PV Costs) x ability of Success		£738,046			



Potential for achieving expected benefits	Project started in September 2011, potential for achieving expected benefits as per above probability of success.
Project Progress to March 12	Stage One of the project to develop a PURL2 prototype has started. Four of the six tasks of stage one have been started.
Collaborative Partners	SP Power Systems, SHEPD, Energy Innovation Centre
R&D Providers	EA Technology Limited



Project Title	IFI 0625 - Vegetatio	n Man	agemei	nt - ADA	S						
	maintenance requir commitment to this growth rates would	regetation management in the vicinity of overhead lines represents a significant maintenance requirement and associated budget spend. While there is an on-going commitment to this issue, it is recognised that a better understanding of vegetation rowth rates would greatly assist in vegetation management strategies and decision making; helping direct the focus of activity.									
Description of project	The project will see between key envir change) and vegeta used to consider the different specification	ronmen tion gro he costs	tal var owth ra	iables( te, for d	includ ifferer	ing the	pote tation	ential types.	impact The mo	of clin del wi	nate II be
	Following tree cutt year of growth data subsequently be op three-year period.	a, which	will be	e determ	nined l	oy lasei	mea	sureme	ent. The	model	will
Expenditure for financial year	Internal	3		Expenditure in previous (IFI) financial years				ternal ternal tal	£3!	1,376 51,537 <b>71,914</b>	
Project Cost (Collaborative + external + SPEN)	£1,744,000		Projected 12/13 costs for SPEN			Ex To	ternal ternal tal	£0 £0			
Technological area and / or issue addressed by project	<ul> <li>This project is a UK wide study into the differing growth rates experienced in the 26 "bio-climatic" zones that are found across the country.</li> <li>It will involve cuts made to 2000 sample areas across the identified zones to a common specification, followed by monitoring to confirm growth.</li> <li>The output is expected to lead to modelling software that can portray different cut cycles.</li> <li>The common UK project should provide further evidence / justification in future Price Control Reviews.</li> </ul>										
Type(s) of innovation involved	Incremental		ignifica	nt		echnolo substitu	-		Rad	Radical	
Expected Benefits of Project	<ul><li>cutting to main</li><li>Evidence-based enhance netw associated regular</li></ul>	<ul> <li>No</li> <li>Yes</li> <li>No</li> <li>No</li> <li>The model developed will identify areas that will require more frequent tree cutting to maintain safe clearance distances and meet legal requirements.</li> <li>Evidence-based decisions on the frequency and location of tree cutting will enhance network resilience and therefore improve security of supply and associated regulatory performance (CI and CML savings).</li> </ul>									
Expected Timescale to adoption	2 Years	J		ion of be				,	20 Year	S	
Probability of Success	75%		TRL Development (Start – Current)  1 2 3 4 5 6 7 8					8	9		
Project NPV	(Present Benefits x Costs	Probabi	lity of S	Success)	– Pres	sent			£681.3l	(	
Potential for achieving expected benefits	The software mode developed software and future vegetation	e model	will he	lp to inf	form d	ecision	-	-			



Project Progress March 12	A full report describing this four year project and its findings was issued in February 2012. The work undertaken determined the average annual growth rate of vegetation with respect to utility space, the physical volume occupied by a utilities facilities and the additional space required to ensure its safe and reliable operation, degradation (USD). Regional variations in USD where calculated with sites located in the warmer areas of southern England, experiencing the average highest rates of vegetation growth and the lowest observed at relatively cooler ScottishPower sites in Scotland. The impact of Climate change predictions out to 2080 on USD across the UK were considered along with different species growth rates. These and other variables that impact the vegetation growth rates were included in a software model that can be used to shape future vegetation strategies in utility areas.
Collaborative	Electricity North West, Scottish and Southern Energy, Central Networks and National
Partners	Grid.
R&D Providers	ADAS



Project Title	IFI 0701 - ENA IFI	Projects			
Description of project		have been init	ion (ENA) represents all iated by the ENA R&D W		=
	Internal	£7,419	Evn and itura in	Internal	£16,516
Expenditure for	External	£7,657	Expenditure in previous (IFI) financial	External	£62,609
financial year	Total	£15,076	years	Total	£79,126
				Internal	£7,500
Project Cost	c£50,0	000	Projected 2012/13	External	£35,000
	0255,5		costs for SP-EN	Total	£42,500
Technological area and / or issue addressed by project	cable and of distribution  Earthing Pro lower voltage resistance of the KEMA "Cook (Energy UK) requirement power sectors of the KEMA Smandevelopment UK electricities.  KEMA Cybert to address Network Opwith new Snow the Medpoint Socurrently in requirement Engage Acceptate network of smart measurement extending the KEMA LCNF Catalogue, for the Innovation projects.  KEMA OTEC presenting the and manage of Smart Gridenergy sceidentifying the techniques	poverhead line of networks. Dject – The ain ge earth electric f distribution so a line of the line of	on electricity networks t.  Develop the first stages of the control of the first stages of the control of the c	iques to assessor zones' and pport a number which deversor to transform of ocus on particular and manager ationally by a kinfrastructure energy provemmon stance tering and smapport the Goacy issues surrethat can be to acy issues.	appropriate for as the impact of to measure the oper of ENA/ERA loped a list of the traditional the impact of indards), on the bundly by these ment framework the Distribution re is developed ission in the UK on investment art grid benefits evernment's low ounding the use aken to mitigate ations managers communications aspirations for the Grid Coverage and Tier 2, and the Zones (RPZ) are sed solutions to the set of UK's future to development, as for smart grid the considers the



Type(s) of	Incremental	Się	gnifica	int		Techno substi	_		ı	Radical	
innovation involved	Yes		Yes			N	0		No		
Expected Benefits of Project	Earthing Project: High. The results from test procedure for measuring t inclusion in a DNO policy do Climate Change and Network The result of this project regard to IIP performance studies and operational processes and operational property in the performance of Cleans and Climate Change and Change an	ransfer locumen rork Res and sub incent eparedi	poter nt. silienc oseque ives w ness fo	e Project Proj	etwee	s will in t on Pr weathe	form fice Corr even	Licensontrols ts.	ee's s , syste	table fo trategy em pla due to	with nning
	penetration of Electric Veh benefits of a smart grid.	licies an	іа неа	it Pum	ips an	ia impa	ct on t	ne nei	twork	and th	e
Expected Timescale to adoption	1 - 10 Years			ation o		efit		10	– 40 Y	ears/	
Probability of			TRL Development (Start – Current)								1
Success	25 - 75%		1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Probab of Success) – Present Costs	-			n calc	f t costs ulated l istribut	by the	e impl ENA a	ssumi		
Project Progress March 12	Project progress is SPinnovation@spenergyne	availab etworks	-	n tl	ne	ENA	websit	te o	r by	/ em	ailing
Potential for achieving expected benefits	Work on the Harmonic harmonics issues on district Earthing Transfer Potentice earthing issues in differing The remaining projects arbenefits explained.	buted n al proje situatio	etwo ects w on.	rks an ill ass	d pro ist tr	duce a ansmiss	revise sion o	d revis	sion o ors to	f G5/4. under	. The stand
Collaborative	National Grid, ScottishPow							thern	Energ	y, Elect	ricity
Partners  R&D Providers	TNEI, Engage Consulti	North West, Western Power Distribution, Northern Powergrid  TNEI, Engage Consulting Limited, Imperial College London, Met Office, EA Technology Ltd, Earthing Solutions, KEMA, Redpoint Energy									



Project Title	IFI 0711 - 3 <sup>rd</sup> Party R	OEP Risk As	sessment					
Description of project	using a new conceptare used, was ach collaboration with Scill risk assessment excategories for Rise of Stage II probabilistic operational clearance. In this project, it implementation of Grid substations (4 relation to the ALA developed to allow the research is to p	The development of the so-called 'Stage I' for risk assessment of earthing systems, using a new concept of safety limit curves, where standard fault clearance times are used, was achieved under National Grid research project NSETS180 in collaboration with Scottish Power, and was completed in Autumn 2006. The Stage risk assessment enables broad classification of substations into low/high risk categories for Rise of Earth Potential (ROEP). The theoretical studies to develop a stage II probabilistic-based risk assessment, which includes the use of historical operational clearance times, are now under development at Cardiff University.  In this project, it is proposed to conduct pilot studies, which allow initial mplementation of the developed 'Stage I' technique at identified key National Grid substations (4 to 5 sites). This will allow a refined quantification of risk in relation to the ALARP levels. In addition, a user-friendly procedure will be developed to allow easy and quick assessment of sites. The ultimate purpose of the research is to provide better information to engineers making decisions on investment for earthing reinforcement schemes.  Internal £ 9,218 Internal £ 30,018						
Expenditure for financial year	External £ 18	86	Expendit previous financial	(IFI)	Internal External	£ 30,018 £ 88,890		
	Total £ 9,	,403			Total	£ 118,909		
Total Project Costs	Total Project Costs  Stage 1 - £100,000 Stage 2 - £150,000			d costs	Internal External Total	£ 10,000 £40,000 £ <b>50,000</b>		
Technological area and / or issue addressed by project		e is a touch/						
Type(s) of innovation involved	Incremental	Project Be Ratin		efits Project Resid		Overall Project Score		
invoived		7			-3	10		
Expected Benefits of Project	There are many sites in Scotland and Manweb where the existing sites do not have earthing that has been installed to the current standard. System fault levels have been increasing due to the significant amounts of renewable generation that has been connected (with bigger schemes in the construction and planning stages). If current system fault levels are applied to these sites there is a potential that the touch/step voltage levels will be too high to allow work to commence without further costly mitigation measure being implemented. This tool would allow an assessment to be made of what the probability would be of a life-threatening fault appearing at the substation so that the appropriate corrective action can be taken. The user friendly interface package will allow SPEN staff to carry out assessments of earthing systems using statistical fault levels and clearance times values as opposed to worst case.  By being better equipped to assess the potential risk posed by existing substation earthing arrangements appropriate steps can be taken, which could be the avoidance of unnecessary expenditure on inappropriate mitigation measures. The software analysis will help to justify Third party mitigation measures.							
Expected Timescale to adoption	1 Year	Dur	ation of b achie		nce	4 Years		



Probability of Success	Project NPV = (PV  75% Benefits – PV Costs) x £ 15,562  Probability of Success							
Potential for achieving expected benefits	<ul> <li>Will incorporated into the set</li> <li>Set up of fault clearance</li> <li>Calculate variation in faindividual risk</li> </ul>	Apply extended computer procedure to several case						
Project Progress March 2012	<ol> <li>This project is now complete. Follow up research works have been commissioned and agreed (April 2012) with Cardiff University to investigate the following:</li> <li>Apply the approach developed in this study to the following situations:         <ul> <li>Potentials exported out with the substation.</li> <li>Locations or point within the substation.</li> </ul> </li> <li>Update the software for revised IEC/CENELEC standards.</li> </ol>							
Collaborative Partners	National Grid							
R&D Provider	Cardiff University High Vol- Huw Griffith).	Cardiff University High Voltage Energy Systems research group (Manu Haddad & Huw Griffith).						



Project Title	IFI 0712 - BT 21 <sup>st</sup> Centui	ry Protectio	on Solutions (	BT21CN)					
Description of project	The change of BT's network to an IP based system (BT21CN) is posing some significant risks to the performance reliability of the SP-M and SP-D electricity networks. In particular SP-M relies heavily on 3 <sup>rd</sup> Party leased services from BT as the communications for the 33kV network protection in rural areas. The strategy to mitigate the problem has been developed based on the utilisation of a range of communications solutions (fibre, radio, power line carrier in addition to technically/commercially suitable BT services) in a coordinated manner. Whilst this strategy has been agreed in principle, there are several technical challenges associated with several of the solutions.  This project aims to provide the detailed and engineered communications channels that underpin the toolbox of solutions to mitigate the problems associated with BT21CN.								
	Internal £14,4	08	- II.		Internal	£ 66,254			
Expenditure for financial year	External £26,3	05	Expenditure previous (IF		External	£ 197,724			
ililaliciai yeal	Total £ 40,7	713	years		Total	£ 264,005			
					Internal	£0			
Total Project Costs	£114,000		Projected 20 costs for SPI		External	£0			
		COSCS TOT ST EIN		Total	£0				
Technological area and / or issue addressed by project	<ul> <li>includes:</li> <li>Power Line Carrier deployment at 33kV combining protection and SCADA signalling</li> <li>Small development works to facilitate intra-substation communications</li> <li>IP based protection signalling mediums and associated security implications</li> <li>Options for alternative communication channels for shared services</li> <li>Implications for the network in no cost effective solutions are realised</li> </ul>								
Type(s) of innovation involved	Significant / Technology Transfer	Ra	ting	Project Residual Ris					
Expected Benefits of Project	There are many sites in SP-M where there is no Line-of-Site for radio communications and fibre installations are extremely expensive due to excessive circuit lengths. In such sites Power Line Carrier (PLC) or Leased services are the only feasible communication mediums for protection signalling. PLC is typically deployed at higher voltage levels, additionally some development work facilitated in a trial would be required to accommodate protection and SCADA data on the same link however this could deliver a more cost effective alternative to fibre or BT SDH leased services. Power Line Carrier although a viable solution has some limitations, which restrict its use on the network, mainly mid-circuit transitions (OHL — Cable), which cause the signals to reflect. Where PLC cannot be deployed alternative will require consideration.  Leased services (or no communications at all) are the only alternatives to expensive infrastructure at some sites. SDH services can be expensive in terms or both CAPEX and OPEX. BT are likely to offer IP based products in the future (products not currently used with protection). If development is carried out to facilitate the use of IP based products for signalling purposes factoring in security considerations then it may be possible to leases services at significantly reduced CAPEX and OPEX costs.								
Expected Timescale to adoption	1.5 Year		Duration of achieved	benefit ond	ce	15 Years			



				TRL De	velopn	nent (S	tart – C	Current	)	
Probability of Success	50%	1	2	3	4	5	6	7	8	9
								<u> </u>		
Project NPV	(Present Benefits x Probability o	of Succe	ss) – Pi	resent	Costs			£951,7	763	
Potential for achieving expected benefits	In areas of the network whe currently considered for use of communications are the communication bearer be unawill be required.	with pr only o	otectio otion.	n devi Shoul	ces wit	hout s suitable	significa e leas	ant exp ed or	ense, l alter	eased native
	In accordance with the output provided the Teleprotection Stewarton.  The circuits have been provide 64Kbps. The circuit has been do than 30 milliseconds.	circuit d by de	betwe	en sul d multi	ostation plexed	n sites chann	locate	ed at l	Kilbirnio Dandwi	e and dth of
Project Progress March 2012	At each end of the circuit, a premises to the most suitable network to the other substatio	Airwa								
	The technical trial of Airwave has concluded however there are significant commercial issues with the productisation of the service by Airwave that have precluded further deployment. The next phase of the project is to establish the feasibility of low cost fibre solutions; so far the use of fibre in sewer pipes has been explored via a desk top exercise with Scottish Water. Unfortunately only sewer pipes of a significant diameter can be considered, these are typically within urban areas SPENs BT 21CN requirements are typically within rural areas and hence there are little or no synergies.									
Collaborative Partners	N/A									
R&D Provider	RFL / C & W / Radius / Tait / o	thers Ti	BC, AIR	WAVE						



Project Title	IFI 0713 - Wide Are	a Monitorin	ng, Protection	on & Control (WA	AMPA	C) for GI	B and IRL		
Description of project	generation sources, introduced complexities to address reactive support and progressively stress transmission networks. This has increased the complexity of operation, monitoring, control and protection of large interconnected electric power systems considerably. The penetration of renewable generation is increasing and there are targets set for connection of future renewable sources. At the same time the Transmission Owner (TO) is faced with an increasing need for construction outages to deliver network reinforcement and existing asset replacement which will result in reduced circuit availability. These factors will lead to much less predictable operating scenarios and therefore greater dependence on real-time support tools to observe and manage the condition of the network.  The increase in this uncertainty could result in transmission instability in the near future, however Wide Area Measurement Systems (WAMS) employing SynchroPhasor Measurement Units (PMUs) are becoming increasingly deployed world wide as a cost effective commercially available technology. A trial using the Psymetrix Phasorpoint Monitoring System will be installed to gather data from up to 15 sites with PMU capability. This will involve the installation of Psymetrix software on a server that will connect to the PMU's and recover in real time phasor data. This data will be stored for post transient evaluation so that system performance can be analysed and determine the frequency modes present in the network. A WEB interface will be installed at the Operational Control Centre (OCC), Cambuslang and Bellshill to evaluate the real time delivery of the data and visualise the system performance in real time and post event.								
	· ·								
Expenditure for	Internal £ 7,	419	Evnanditu	re in previous	Inter	nal	£ 16,537		
financial year		2,339	(IFI) financ		External		£ 5,060		
	Total £ 6	9,757			Tota		£ 21,597		
			Draiactad	2012/13 costs	Inter	nal	£5,000		
Total Project Costs	£ 59,715		for SPEN	Exte	mal	£ 27,000			
					Tota		£ 32,000		
Technological area and / or issue addressed by project	SPT is obliged under its licence and the Electricity Act to develop an efficient, co- ordinated and economic system of electricity supply.  Power-grid congestion issues and disturbances worldwide have emphasized the need to enhance power grids with smart applications (SmartGrids, Flexnet, and Intelligrid), providing decision support to operators and automation to ensure optimum use of assets, whilst maintaining system security and plant and circuit thermal limits. This work will support the development of next generation data and communications infrastructures for smart applications.								
Type(s) of innovation involved	Incremental	-	Benefits Project Resid ting Risk				rall Project Score		
involveu	inter entrental		.3	-9		22			



Expected Benefits of Project	<ul> <li>As a safety net for the particularly on the Enunderstanding of the transmission networks, changing generation and</li> <li>Knowledge of the curresmart protection, confinetwork is ready and SmartGrid and Intelligric</li> <li>The successful application managing the risks an renewable and intermit</li> <li>A better understanding of available network casafely within its capabili</li> <li>This project has the pott identifying a very high informed asset manage</li> <li>The project will support of existing assets and Remedial Action schemostraints.</li> <li>Typically the Financial B infrastructure reinforced programme.</li> </ul>	ngland- currer cons d dema ent net crol ar able d initia on of V nd op tent ge of sys apacity ty and ential impace ment. the sy l prov es, wh	Scotlant capidering and particular to actives. Vide Arportunineration to create, low stem ride and indicated are actives.  will be will be will be will be are active are are actives.	nd in ability constiterns. condition common construction. In limits ate a contruction alternation alternation alternation construction construction construction construction alternation alternation alternation construction alternation	terface and traints ions with the politorinand to ans and aints a ost effective to the comment of the comment o	t programment of the country of the	is acty of mitter w futures and general tate to be taken to be tak	chieved the G the G nt gen re devid will ation i ne a ma the co l enabl nat pla d of pr ntribut , ensur onal T ermal	I by I B and eration elopme ensure n line ajor facente ebette edictine es to I be to es to I be to estand state estment	ent of en
Expected Timescale to adoption	4 Years	Durat achie		benefi	t once			10 Ye	ars	
			1	TRL De	velopn	nent (S	tart – (	Curren	t)	
Probability of Success	75%	1	2	3	4	5	6	7	8	9
								$\geq$		
Project NPV	(Present Benefits x Probabili Present Costs	ty of S	uccess)	) –	No NPV	' calcul	ated fo	or this	imited	trial
Project Progress March 2012	The University of Mancheste the PhD thesis summary due			been	extend	led for	a furt	her 6 r	nonths	, with
Potential for achieving expected benefits	While existing network development and management is well developed, increasing operating uncertainties due to increasing renewable penetration will lead to a greater dependence on real-time support tools.									
Collaborative Partners		National Grid, Scottish Power, Scottish and Southern Electricity, Northern Ireland Electricity and ESBI (Ireland).								eland
R&D Provider	University of Manchester Areva, Siemens and ABB who	o will s	upply a	and ins	stall the	e phase	or mea	surem	ent uni	ts.



retrofitting (refurbishment) projects to proceed whilst limiting the duration and frequency of circuit outages, required to facilitate the work.  Internal £8,750 External £36,863 Total £45,612  Total project Costs  Expenditure in previous (IFI) External £36,863 Expenditure in previous (IFI) Financial years  Faternal £4,000 External £4,000 External £12,000 Total Project 1 (IFI 0801-1) – Microsol  This proposal is twofold, to develop, test and commission the IEC Protocol on the Microsol RTU to allow us to trial interfacing to two specific devices at two specific locations, namely:  a) Busby 275kV Hathaway Fault Recorder. b) Strathaven 400kV Operational Intertripping Relay.  At Busby 275kV we propose to recover all the Analogue information from the fault recorder, this will allow us not only to present more information to the Control Engineers in real time, it will eliminate any issues with faulty transducers, faulty resistor scaling and faulty wiring.  Technological area and / or issue addressed by project  This IFI application aims to investigate, quantify and optimise the level of security, dependability and speed in secondary schemes using IEC 61850. This project is strategically aligned with Iberdrola Networks and will provide procurement benefits.  Project3 (IFI 081-3) – "Hardfibre" Process Bus Field Trial & RTDS Testing  GE Multilin are first to market with IEC61850-9-2 products and the proposal is to undertake a field trial at the new Inverarnan 275kV substation and to perform RTDS testing of the scheme. This will achieve the following objectives: Proof that the protection performance of a process bus system is at least equal to conventional schemes To gain experience of the installation, configuration and operation of a process bus system.  To measure the time and cost benefits of process bus.	Project Title	IFI 0801 - IEC 618	50 Application in SP -	Transmission						
External £36,863 Total £45,612  External £36,863 Total £45,612  External £36,863 Total £45,612  External £40,000 External £40,000 External £40,000 External £12,000 Total £40,000 External £12,000 Total £10,000  Project 1 (IFI 0801-1) — Microsol  This proposal is twofold, to develop, test and commission the IEC Protocol on the Microsol RTU to allow us to trial interfacing to two specific devices at two specific locations, namely:  a) Busby 275kV Hathaway Fault Recorder. b) Strathaven 400kV Operational Intertripping Relay.  At Busby 275kV we propose to recover all the Analogue information from the fault recorder, this will allow us not only to present more information to the Control Engineers in real time, it will eliminate any issues with faulty transducers, faulty resistor scaling and faulty wiring.  Technological area and / or issue addressed by project  This IFI application aims to investigate, quantify and optimise the level of security, dependability and speed in secondary schemes using IEC 61850. This project is strategically aligned with Iberdrola Networks and will provide procurement benefits.  Project3 (IFI 081-3) — "Hardfibre" Process Bus Field Trial & RTDS Testing  GE Multillin are first to market with IEC61850-9-2 products and the proposal is to undertake a field trial at the new Inverarnan 275kV substation and to perform RTDS testing of the scheme. This will achieve the following objectives: Proof that the protection performance of a process bus system is at least equal to conventional schemes To gain experience of the installation, configuration and operation of a process bus system. To measure the time and cost benefits of process bus.	Description of project	of the transmissi advocated for this retrofitting (refur	on asset and netwo s IFI project will allow bishment) projects to	rk. The deployme ongoing substation proceed whilst lim	ent of the secondary iting the du	technology equipment				
Total Fab, 803 financial years  Total Fab, 802 financial years  Fab, 803 financial years  Fab, 802 financial fab, 902 fi		Internal £8,75			Internal	£24,937				
Total Project Costs  £455,000  Projected 2012/13 costs for SPEN  Project 1 (IFI 0801-1) – Microsol  This proposal is twofold, to develop, test and commission the IEC Protocol on the Microsol RTU to allow us to trial interfacing to two specific devices at two specific locations, namely:  a) Busby 275kV Hathaway Fault Recorder. b) Strathaven 400kV Operational Intertripping Relay.  At Busby 275kV we propose to recover all the Analogue information from the fault recorder, this will allow us not only to present more information to the Control Engineers in real time, it will eliminate any issues with faulty transducers, faulty resistor scaling and faulty wiring.  Project 2 (IFI 0801-2) - University of Manchester and NGC  This IFI application aims to investigate, quantify and optimise the level of security, dependability and speed in secondary schemes using IEC 61850. This project is strategically aligned with Iberdrola Networks and will provide procurement benefits.  Project3 (IFI 081-3) - "Hardfibre" Process Bus Field Trial & RTDS Testing  GE Multilin are first to market with IEC61850-9-2 products and the proposal is to undertake a field trial at the new Inverarnan 275kV substation and to perform RTDS testing of the scheme. This will achieve the following objectives: Proof that the protection performance of a process bus system is at least equal to conventional schemes To gain experience of the installation, configuration and operation of a process bus system. To measure the time and cost benefits of process bus.	Expenditure for financial year	External £36,8	h-4		External	£65,271				
Total Project Costs  £455,000  Project 1 (IFI 0801-1) – Microsol  This proposal is twofold, to develop, test and commission the IEC Protocol on the Microsol RTU to allow us to trial interfacing to two specific devices at two specific locations, namely:  a) Busby 275kV Hathaway Fault Recorder. b) Strathaven 400kV Operational Intertripping Relay.  At Busby 275kV we propose to recover all the Analogue information from the fault recorder, this will allow us not only to present more information to the Control Engineers in real time, it will elliminate any issues with faulty transducers, faulty resistor scaling and faulty wiring.  Project 2 (IFI 0801-2) - University of Manchester and NGC  This IFI application aims to investigate, quantify and optimise the level of security, dependability and speed in secondary schemes using IEC 61850. This project is strategically aligned with Iberdrola Networks and will provide procurement benefits.  Project3 (IFI 081-3) - "Hardfibre" Process Bus Field Trial & RTDS Testing  GE Multillin are first to market with IEC61850-9-2 products and the proposal is to undertake a field trial at the new Inverarnan 275kV substation and to perform RTDS testing of the scheme. This will achieve the following objectives: Proof that the protection performance of a process bus system is at least equal to conventional schemes To gain experience of the installation, configuration and operation of a process bus system. To measure the time and cost benefits of process bus.  Type(s) of innovation involved    Incremental   Project Benefits   Project Residual   Overall Project   Score		Total £45,6	12		Total	£90,209				
Project 1 (IFI 0801-1) – Microsol  This proposal is twofold, to develop, test and commission the IEC Protocol on the Microsol RTU to allow us to trial interfacing to two specific devices at two specific locations, namely:  a) Busby 275kV Hathaway Fault Recorder. b) Strathaven 400kV Operational Intertripping Relay.  At Busby 275kV we propose to recover all the Analogue information from the fault recorder, this will allow us not only to present more information to the Control Engineers in real time, it will eliminate any issues with faulty transducers, faulty resistor scaling and faulty wiring.  Project 2 (IFI 0801-2) - University of Manchester and NGC  This IFI application aims to investigate, quantify and optimise the level of security, dependability and speed in secondary schemes using IEC 61850. This project is strategically aligned with Iberdrola Networks and will provide procurement benefits.  Project3 (IFI 081-3) - "Hardfibre" Process Bus Field Trial & RTDS Testing  GE Multilin are first to market with IEC61850-9-2 products and the proposal is to undertake a field trial at the new Inverarnan 275kV substation and to perform RTDS testing of the scheme. This will achieve the following objectives: Proof that the protection performance of a process bus system is at least equal to conventional schemes To gain experience of the installation, configuration and operation of a process bus system.  To measure the time and cost benefits of process bus.  Type(s) of innovation involved  Incremental Tech Transfer Score				2042/42	Internal	£4,000				
Project 1 (IFI 0801-1) – Microsol  This proposal is twofold, to develop, test and commission the IEC Protocol on the Microsol RTU to allow us to trial interfacing to two specific devices at two specific locations, namely:  a) Busby 275kV Hathaway Fault Recorder. b) Strathaven 400kV Operational Intertripping Relay.  At Busby 275kV we propose to recover all the Analogue information from the fault recorder, this will allow us not only to present more information to the Control Engineers in real time, it will eliminate any issues with faulty transducers, faulty resistor scaling and faulty wiring.  Technological area and / or issue addressed by project  This IFI application aims to investigate, quantify and optimise the level of security, dependability and speed in secondary schemes using IEC 61850. This project is strategically aligned with Iberdrola Networks and will provide procurement benefits.  Project3 (IFI 081-3) – "Hardfibre" Process Bus Field Trial & RTDS Testing  GE Multilin are first to market with IEC61850-9-2 products and the proposal is to undertake a field trial at the new Inverarnan 275kV substation and to perform RTDS testing of the scheme. This will achieve the following objectives: Proof that the protection performance of a process bus system is at least equal to conventional schemes To gain experience of the installation, configuration and operation of a process bus system.  To measure the time and cost benefits of process bus.  Type(s) of innovation involved  Incremental Project Benefits Project Residual Score	Total Project Costs	£455,000			External	£12,000				
This proposal is twofold, to develop, test and commission the IEC Protocol on the Microsol RTU to allow us to trial interfacing to two specific devices at two specific locations, namely:  a) Busby 275kV Hathaway Fault Recorder. b) Strathaven 400kV Operational Intertripping Relay.  At Busby 275kV we propose to recover all the Analogue information from the fault recorder, this will allow us not only to present more information to the Control Engineers in real time, it will eliminate any issues with faulty transducers, faulty resistor scaling and faulty wiring.  Project 2 (IFI 0801-2) - University of Manchester and NGC  This IFI application aims to investigate, quantify and optimise the level of security, dependability and speed in secondary schemes using IEC 61850. This project is strategically aligned with Iberdrola Networks and will provide procurement benefits.  Project3 (IFI 081-3) - "Hardfibre" Process Bus Field Trial & RTDS Testing  GE Multilin are first to market with IEC61850-9-2 products and the proposal is to undertake a field trial at the new Inverarnan 275kV substation and to perform RTDS testing of the scheme. This will achieve the following objectives: Proof that the protection performance of a process bus system is at least equal to conventional schemes To gain experience of the installation, configuration and operation of a process bus system. To measure the time and cost benefits of process bus.  Type(s) of innovation involved  Incremental Tech Transfer Significant  Project Benefits Rating Project Residual Risk Score					Total	£16,000				
Microsol RTU to allow us to trial interfacing to two specific devices at two specific locations, namely:  a) Busby 275kV Hathaway Fault Recorder. b) Strathaven 400kV Operational Intertripping Relay.  At Busby 275kV we propose to recover all the Analogue information from the fault recorder, this will allow us not only to present more information to the Control Engineers in real time, it will eliminate any issues with faulty transducers, faulty resistor scaling and faulty wiring.  Technological area and / or issue addressed by project  This IFI application aims to investigate, quantify and optimise the level of security, dependability and speed in secondary schemes using IEC 61850. This project is strategically aligned with Iberdrola Networks and will provide procurement benefits.  Project3 (IFI 081-3) – "Hardfibre" Process Bus Field Trial & RTDS Testing  GE Multilin are first to market with IEC61850-9-2 products and the proposal is to undertake a field trial at the new Inverarnan 275kV substation and to perform RTDS testing of the scheme. This will achieve the following objectives: Proof that the protection performance of a process bus system is at least equal to conventional schemes To gain experience of the installation, configuration and operation of a process bus system. To measure the time and cost benefits of process bus.  Type(s) of innovation involved  Incremental Tech Transfer Significant  Project Benefits Rating Project Residual Score		Project 1 (IFI 0802	l-1) – Microsol							
At Busby 275kV we propose to recover all the Analogue information from the fault recorder, this will allow us not only to present more information to the Control Engineers in real time, it will eliminate any issues with faulty transducers, faulty resistor scaling and faulty wiring.  Project 2 (IFI 0801-2) - University of Manchester and NGC  This IFI application aims to investigate, quantify and optimise the level of security, dependability and speed in secondary schemes using IEC 61850. This project is strategically aligned with Iberdrola Networks and will provide procurement benefits.  Project3 (IFI 081-3) - "Hardfibre" Process Bus Field Trial & RTDS Testing  GE Multilin are first to market with IEC61850-9-2 products and the proposal is to undertake a field trial at the new Inverarnan 275kV substation and to perform RTDS testing of the scheme. This will achieve the following objectives: Proof that the protection performance of a process bus system is at least equal to conventional schemes  To gain experience of the installation, configuration and operation of a process bus system.  To measure the time and cost benefits of process bus.  Type(s) of innovation involved  Type(s) of innovation involved										
fault recorder, this will allow us not only to present more information to the Control Engineers in real time, it will eliminate any issues with faulty transducers, faulty resistor scaling and faulty wiring.  Project 2 (IFI 0801-2) - University of Manchester and NGC  This IFI application aims to investigate, quantify and optimise the level of security, dependability and speed in secondary schemes using IEC 61850. This project is strategically aligned with Iberdrola Networks and will provide procurement benefits.  Project3 (IFI 081-3) - "Hardfibre" Process Bus Field Trial & RTDS Testing  GE Multilin are first to market with IEC61850-9-2 products and the proposal is to undertake a field trial at the new Inverarnan 275kV substation and to perform RTDS testing of the scheme. This will achieve the following objectives: Proof that the protection performance of a process bus system is at least equal to conventional schemes To gain experience of the installation, configuration and operation of a process bus system. To measure the time and cost benefits of process bus.  Type(s) of innovation involved  Froject Benefits Project Residual Overall Project Residual Rating Risk Score										
This IFI application aims to investigate, quantify and optimise the level of security, dependability and speed in secondary schemes using IEC 61850. This project is strategically aligned with Iberdrola Networks and will provide procurement benefits.  Project3 (IFI 081-3) – "Hardfibre" Process Bus Field Trial & RTDS Testing  GE Multilin are first to market with IEC61850-9-2 products and the proposal is to undertake a field trial at the new Inverarnan 275kV substation and to perform RTDS testing of the scheme. This will achieve the following objectives: Proof that the protection performance of a process bus system is at least equal to conventional schemes To gain experience of the installation, configuration and operation of a process bus system. To measure the time and cost benefits of process bus.  Type(s) of innovation involved  Type(s) of innovation involved  Type(s) of innovation involved		At Busby 275kV we propose to recover all the Analogue information from the fault recorder, this will allow us not only to present more information to the Control Engineers in real time, it will eliminate any issues with faulty transducers, faulty resistor scaling and faulty wiring.								
This IFI application aims to investigate, quantify and optimise the level of security, dependability and speed in secondary schemes using IEC 61850. This project is strategically aligned with Iberdrola Networks and will provide procurement benefits.  Project3 (IFI 081-3) – "Hardfibre" Process Bus Field Trial & RTDS Testing  GE Multilin are first to market with IEC61850-9-2 products and the proposal is to undertake a field trial at the new Inverarnan 275kV substation and to perform RTDS testing of the scheme. This will achieve the following objectives: Proof that the protection performance of a process bus system is at least equal to conventional schemes To gain experience of the installation, configuration and operation of a process bus system. To measure the time and cost benefits of process bus.  Type(s) of innovation involved  Type(s) of innovation involved  Type(s) of innovation involved	Technological area and	Project 2 (IFI 0801-2) - University of Manchester and NGC								
GE Multilin are first to market with IEC61850-9-2 products and the proposal is to undertake a field trial at the new Inverarnan 275kV substation and to perform RTDS testing of the scheme. This will achieve the following objectives: Proof that the protection performance of a process bus system is at least equal to conventional schemes  To gain experience of the installation, configuration and operation of a process bus system.  To measure the time and cost benefits of process bus.  Type(s) of innovation involved  Project Benefits Project Residual Overall Project Residual Score Significant	/ or issue addressed by project	This IFI application aims to investigate, quantify and optimise the level of security, dependability and speed in secondary schemes using IEC 61850. This project is strategically aligned with Iberdrola Networks and will provide procurement benefits.								
undertake a field trial at the new Inverarnan 275kV substation and to perform RTDS testing of the scheme. This will achieve the following objectives:  Proof that the protection performance of a process bus system is at least equal to conventional schemes  To gain experience of the installation, configuration and operation of a process bus system.  To measure the time and cost benefits of process bus.  Type(s) of innovation involved  Project Benefits Rating Project Residual Score  Rating Risk Score		Project3 (IFI 081-	3) – "Hardfibre" Proce	ess Bus Field Trial &	RTDS Test	ing				
Type(s) of innovation involved  Tech Transfer Significant  Rating Risk Score		Proof that the protection performance of a process bus system is at least equal to conventional schemes  To gain experience of the installation, configuration and operation of a process bus system.								
Significant	Type(s) of innovation	Tech Transfer				=				
		Significant	17	-7	7	24				



Expected Benefits of Project	flexibility for the future as substation design and choose advantage of allowing us with multi-core copper cab. LAN approach to comms as However, IEC61850 also GOOSE services has been escheme) to provide sign significantly reduced instanctionality can be factor process bus which can,	commissioned successfully on our Microsol RTU then it gives us some real flexibility for the future and will fundamentally influence decisions regarding substation design and choice of relay manufacturer, and will have the added advantage of allowing us to cease the highly expensive option of flood wiring with multi-core copper cables within the substation environment and adopting a LAN approach to comms and data capture.  However, IEC61850 also offers benefits in the protection realm. The use of GOOSE services has been demonstrated (in the West Coast operational Intertrip scheme) to provide significant performance benefits over hard-wiring and significantly reduced installation and testing times as much of the scheme functionality can be factory tested. Additionally, part 9-2 permits the use of a process bus which can, in addition to reduced wiring, provide additional reliability and the future promise of outage-free protection replacement.										
Expected Timescale to adoption	1 Year	Duration of benefit once achieved 10 Years										
	TRL Development (Start – Current)											
Probability of Success	75%	1 2 3 4 5 6 7 8						8	9			
Project NPV	(Present Benefits x Probab	ility of	Succe	:ss) — P	resent	Costs			calcula imited			
Potential for achieving expected benefits	The University project Eval Substation Protection and final report due mid 2012. It is hoped than the learning in the use of IEC61850	Contr	ol Rel	iability	is no	w com	ning to	a clo	se wit	h the		
Project Progress March 2012	Project 1 and 3 are now c some work to be carried or			•					here i	s still		
Collaborative Partners	Project 1 and 3 none, Proje	ect 2 N	1anche	ester L	Inivers	ity, SS	E, NG	2				
R&D Provider	Manchester University											



Project Title	IFI 1001 – Offline Plan	nina Tool for Dynd	mic Thermal Rat	ina							
	The dynamic thermal				ation that the first						
	limit for the current carrying capacity of a circuit is its temperature, influenced by its										
	ability to dissipate to the environment the heat produced by the joule effect, and by										
Description of project	external conditions				•						
	constantly varying. Even though the mechanisms of heat exchange involved are well										
	understood, determination of the correct value of the circuit temperature is non-										
	trivial. For this reason,	, static ratings base	d on the worst ca	se scenar	io are often used.						
Expenditure for	Internal £17,539	9 Evnenditur	e in previous	Internal	£6,092						
financial year	External £10,186	6 (IFI) financi	•	External	£11,700						
iniancial year	Total £27,72	4 (111) 111141161	ui yeuis	Total	£17,793						
		Projected 1	2/13 costs for	Internal	- /						
Project Cost	£121,500	SPEN	2/13 (03(3 10)	External	,						
				Total	£13,000						
	The implementation	-									
	increases its average										
	overload. However, su										
	overcome. Not least										
Table alsoinel and	component temperatu										
Technological area and / or issue	area containing a sign	ificant number of p	ower system cor	nponents	distributed around						
addressed by project	a complex terrain.	a complex terrain.									
addressed by project	A successful DTR system could be used as a decision support tool for Distribution										
	Network Operators (DNO). This tool could be used both at the planning stage and in										
	network Operators (DNO). This tool could be used both at the planning stage and in real time within potential future active network management philosophies in order to										
	safely increase the utilization of power systems and facilitate distributed generation										
	(DG).	•	•		J						
	Incremental	Significant	gical	Radical							
Type(s) of innovation	merementar	substitution			Nadicai						
involved	No	No	Yes		No						
		re already working with Scottish Power and Astrium on a TSB									
	project to investigate the use of DTRs for electrical distribution networks in order to										
	accommodate increased levels of DG safely and cost effectively.										
	The aim of this phase of the work is to carry out further research and development										
	work to build upon the achievements so far, ensure continuity and to avoid the loss of										
	vital knowledge gained by the PhD researchers. The primary deliverable will be an offline tool to:										
	offiline tool to:										
	1. Allow SP plannin	g engineers to ev	aluate the likely	headroo	m which could be						
					ange of existing SP						
	distribution netwo		7		0 0 1 1 0 1						
Expected Benefits of			nd meteorologic	al data ac	well as terrain and						
Project	vegetation inform		na meteorologica	ai uata as	well as terrain and						
	_				l +						
		•	. •		transformers over						
			•		es in the form of a						
	probability distribution function. (In this document 'Distribution Network' refers										
		voltages up to and	_	-							
					configurations of						
		nderground cables									
	5. Allow calculations to be made regarding the potential additional energy that										
	could be accom	modated by the	power system	when dy	namic ratings are						
	adopted.										
	<u>'</u>										



Expected Timescale to adoption	4 Years	Duration of benefit once achieved					10 Years				
	Draiosts with various		T	TRL De	velopn	nent (S	tart – C	Current	t)		
Probability of Success	Projects with various probabilities of success will	1	2	3	4	5	6	7	8	9	
	be considered						•				
Project NPV	(Present Benefits x Probability of Success) – Present Costs £58,587										
Project Progress  March 12	Significant simulation work computational fluid dynami mapping (primarily height behaviour. The current work tables based on the above, inverse distance interpolations sensitivity analysis is being considerated accuracy of the new estimation of the property of the sensitivity analysis is being considerated accuracy of the new estimation of the sensitivity analysis is being employed in order to consider the sensitivity analysis is being employed in order to consider the sensitivity analysis is being employed in order to consider the sensitivity analysis is being the sensitivity analysis is sensitivity analysis.	c (CFD and sk is focwith to metor and size of the control of the c	) techrurface ussing the ain thod of out to orithm	rough on deven of each of wind identifus and	and honess) veloping nhanci speed y the k further	igh resign or one of the or of the of	solution der to I-speed accura tion es tors wh	mode mode d/directacy of timation nich de	ain toped the tion loot the cuon. Further the cuote the cuote the cuote the terminal	wind ok-up urrent urther ne the	
Potential for achieving expected benefits	Having an offline planning tool for analysing the dynamic ratings of circuits will enhance our ability in understanding the impact of utilising these technique in real time and power flow analysis. The tool will assist in the analyses and management of constraints in the network and also support design engineers to make informed decisions with regards to enhanced dynamic rating for circuits and their impact on the network, power flow and constrains on embedded generation.										
Collaborative Partners	Astrium, Durham University										
R&D Providers	Durham University										



Project Title	IFI 1002 - Superge	n HiDEF										
Description of project	The Highly Distrib that will demons enables all end us and thereby more resources to delive	trate a r ers to par fully expl	adical ticipat loits th	vision o e in syst e potent	of a l em o <sub>l</sub> :ial of	nighly peratio distrib	distrib on and uted g	uted e real tir enerat	energy ne ene ion and	future ergy ma d active	that arkets e load	
Expenditure for financial year	Internal £14 External £5,1	,075	Expe	nditure i inancial	n pre	vious	In Ex	ternal ternal <b>otal</b>		£6,092 £15,380 <b>£21,472</b>		
Project Cost	+4 497 000			Projected 12/13 costs for SPEN				ternal ternal <b>otal</b>		£3,000 £20,00 <b>£23,00</b>	0	
Technological area and / or issue addressed by project	relating to key questions of current concern within the stakeholder community and in this way its relevance extends beyond the limits of its decentralised system vision. In concept, the research vision is one of decentralised resources, control and market participation extending to include end users at system extremities.											
Type(s) of innovation involved	Incremental Sig			int		Fechno substit	-		R	adical		
invoived	Yes		No			N	0			No		
Expected Benefits of Project	impact of  The impa  and cont	ent into oss the sugement version of a future act of a defact of a defact of a defact of a	the furpply chair of the contract of the contr	ture of nain. In g ademia ralised s alised sy	netw genera and in ystem stem	vork s al the b ndustr n. on net	ystems penefit y into works	and s will e the un infrast	the ir ntail: derstai	ifluenc nding o	es of of the ration	
Expected Timescale to Adoption	9 years			ition of k eved	oenefi	it once			7 yea	ırs		
				TI	RL De	velopn	nent (S	tart – C	Current	:)		
Probability of Success	25%		1	2	3	4	5	6	7	8	9	
Project NPV	(Present Benefits x Probability of Success) – Present Costs							£78,648				
Project Progress March 2012	PV Penetration study — a study and working tool has been developed to enable planners to quickly assess the impact of connecting small scale PV in housing estates in the Manweb area. This report has now been delivered along with an Excel based PV voltage rise tool that has been used by SP Manweb to allocate >2,000 'clustered' PV installations.											



Potential for achieving expected benefits	SP Distribution and SP Manweb networks, and to some extent SP Transmission will benefit from the insight into a power network well into the future and the challenges that it might bring. It is envisaged that this applied research project will be useful for future Price Control discussions, particularly in the areas of smart applications, regulatory and commercial structures.  The project is academic in nature but at the same time taking into consideration current developments in areas such as smart meters, demand side management and micro generation among many others.  Project Addition The PV report and voltage rise tool has been used by SP Manweb to allocate >2,000 'clustered' PV installations delivering significant benefit to SP Manweb and the UKs energy targets.
Collaborative Partners	EDF, Areva, Rolls Royce and many other SMEs
R&D Providers	University of Strathclyde (Lead), Imperial College, Oxford University, Cardiff University, University of Bath



Project Title	IFI 1003 - Strategic A	Asset Lij	fecycle Value O	ptimisation "S	ALVO"					
Description of project	It is estimated that there is £200bn of identified investment requirements in UK core infrastructure during the next 10-20 years and that evidence suggests up to 30% of total asset life cycle costs could be avoided by better decision making. SALVO aims to develop simple, flexible and practical guidance and tools for determining what to spend and when.  A consortium of "Core Participants" is currently being set up to progress the project which will have workstreams in the "start of life", "utilisation and maintenance" and "managing aging assets" phases of the asset life cycle. SP EnergyNetworks is joining the project as an "Associate". This will allow SP EnergyNetworks early sight of the outputs of the project and an opportunity to influence them. The cost of this project membership is £5k.									
	It is anticipated that the project will provide spin off to SP EnergyNetworks in improving the optimisation of spend and managing the lifecycle of the assets through the tools developed by the project consortium.									
	The project duration		ars.		Γ					
Expenditure for	Internal £9,416	5	Expenditure ii	n previous	Interna	,				
financial year	External £186		(IFI) financial	-	Externa	,				
	Total £9,601	<u> </u>			Total	£18,002				
Project Cost			Projected 12/	13 costs for	Interna	-				
(Collaborative +	£960,000		SPEN	13 00313 101	Externa	ol £0				
external + SPEN)	The project aims t				Total	£0				
Technological area and / or issue addressed by project	renewal)	n health degrada evention mised, cicularly	n/ criticality defition and risk ch in justifications total system p	initions and dia naracteristics (inspection, erformance an ng integrated s	gnosis maintena d work p					
Type(s) of innovation	Incremental	S	ignificant	Technolog substituti		Radical				
involved	No		Yes	No		No				
Expected Benefits of Project	<ul> <li>Collate existing best practice processes and available tools</li> <li>Identify the realistic range of scenarios, options, decision types, data, information and assumption requirements, cost/risk/benefit evaluations and calculations, results interpretation, decision making and conclusions and implementation processes</li> <li>Develop a series of decision templates</li> <li>Update and integrate suitable decision support tools for the cost/benefit/risk quantification and optimisation steps, including generic interface design for different data sources and facilities for export of results into work planning and management systems</li> <li>Develop and publish a series of worked case studies of the application of these processes and tools</li> </ul>									



Expected Timescale to Adoption	3 years	Dura achie	tion of ved	benefi	t once		7 years				
			٦	TRL De	velopn	nent (S	tart – C	Current	:)		
Probability of Success	75%	1	2	3	4	5	6	7	8	9	
				l							
Project NPV	(Present Benefits x Probabil Present Costs										
Project Progress March 12	This project is now closed										
Potential for achieving expected benefits	Improvement in the management of asset base is likely to lead to a reduction in risks of plant and equipment failure and increase safety for staff and members of the public.										
Collaborative Partners	Core Sponsors: National Grid, ScottishWater, London Underground, Cambridge University Associates: SASOL, Forbo Nairn, Gatwick Airport										
R&D Providers	The Woodhouse Partnership	and D	ecisior	Supp	ort Tod	ols					



Project Title	IFI 1004 - Remote A	ccess to	Pole N	lounte	d Auto	Reclo	sers					
	The Noja pole mounted auto recloser incorporates a protection module, the MPM, which can be accessed to retrieve active and historical data relating to both protection activity and statistical metering.											
Description of project	This can only be a mounted below the climber. Access to tadvantage if addition to ascend the pole.	e Main his pane	Tank, d el requi	out wit res a s	h the peciali	Safety st skill	Distar . It wo	nce, an uld a b	id abov ousiness	e the and s	Anti- safety	
	The proposal from remote access of th				-	_		nvoy'ı	module	to a	Noja,	
	Nortech has proved that the ENVOY can talk to the NOJA, but this needs to be p in an operational situation.									be pı	roved	
Expenditure for financial year	Internal £14,8 External £37,1 Total £51,9	06	Expenditure in previous (IFI) financial years				Ex	iternal kternal <b>otal</b>	f	0 0 2 <b>0</b>		
Project Cost (Collaborative + external + SPEN)	<b>£76,800</b> Projected 12/13 co				Interr Exterr Total			f10,000 fnal £25,000		0		
Technological area and / or issue addressed by project	The project aims to address the issue of safe and automated remote access to active and historical data from SPEN's population of Noja PMAR.  The project will enable circuits to be ranked accordingly to agreed performance indicators e.g. circuits with most trips which could inform operational and maintenance activities.											
Type(s) of innovation	Incremental	Si	gnifica	nt		echno substit	logical tution	l Radio			dical	
involved	Yes		No			No				No		
Expected Benefits of Project	<ul> <li>access informat</li> <li>Automatic collesite and conseq</li> <li>Summary analyoperations</li> </ul>	site and consequent delays in getting data  • Summary analysis of PMAR activity with dashboard showing league table of										
Expected Timescale to Adoption	3 years		Dura achie	tion of ved	benefi	t once			10 yea	ırs		
Probability of Success	50%		TRL Developm					tart – (	7	8	9	
Project NPV	(Present Benefits x Probability of Success) – Present Costs  £343,820											



Project Progress March 12	There have been some issues around the communication between the Noja controller and the Nortech envoy.  This issue should be resolved in early may and the 30 units should then be able to be installed on the live network.
Potential for achieving expected benefits	By being able to see system events almost real time, this should be able to give operational engineers an enhanced view of any abnormal events without having to go out on site.
Collaborative Partners	None
R&D Providers	Nortech



Project Title	IFI 1005 - GIS Imped	ence M	apping	- zMap	,								
Description of project	Carrying on from tl Monitor using Web obtained from sub.n mapping software.	System	s, it is	propos	ed to	utilise	the vo	oltage a	and cu	rrent v	alues ′		
Expenditure for financial year	Internal £14,07 External £35,04 Total £49,13	13	-	iditure nancial	-		Ex	Internal External <b>Total</b>		£11,302 £6,700 £18,002			
Project Cost	£130,520		Projected 2012/13 costs for SPEN					ternal cternal <b>otal</b>		£0 £0 <b>£0</b>			
Technological area and / or issue addressed by project	that we currently u values per cable type Currently SP have ro only polled once a d to be emailed to a us As the new ENMAC i	The laborious process of tracing a circuit length will be obsolete with the GIS platform that we currently use able to trace via impedance based on a table of impedance values per cable type.  Currently SP have roughly 200 PQR that are able to record faults, but these units are only polled once a day or on an ad hoc basis. This project will enable fault information to be emailed to a user or iHost which can then deduce and impedance value.  As the new ENMAC is currently some time away its imperative that a frontend for new IFI projects and current IFI projects is developed to ease the transition into SPENs SCADA network.											
Type(s) of innovation	Incremental	Si	gnifica	nt		Technological substitution			Radical				
involved	No	Yes				N	0			No			
Expected Benefits of Project	<ul> <li>The existing GeoField Network Map Viewer tracing engine will be configured to allow tracing from a start point to a specified accumulated impedance value. This will behave in an identical fashion to the existing length-based trace.</li> <li>Integration to implement a scheme for SP Power Systems to allow PQRs to trigger autocomms for retrieval of fault records using email. This is required because SP current IT policies do not allow modems to answer incoming calls and the only way to retrieve data from recorders is to use autopoll, automatic or manual.</li> </ul>												
Expected Timescale to Adoption	2 years		Durat achie	tion of ved	benefi	it once			10 ye	ars			
						1	1	nt (Start – Current)					
Probability of Success	50%		1	2	3	4	5	6	7	8	9		
Project NPV	(Present Benefits x I Present Costs	Probabil	lity of S	uccess	) <b>–</b>			£151	1,554				
Project Progress March 2012	This project has no within the control ro	oms. and ope	erate 3	0 subst	ation	disturb	ance r	ecorde	rs fron	n Embe	edded		
Potential for achieving expected benefits	Monitoring Systems retrieved from the receiving e-mails ser inputs.  By using the data from the potential.	sub.net nt by th	device e devic	e eithe e in re	r by i	using a e to ev	ın inbı ents o	uilt we ccurrin	b inte g on it	rface, s moni	or by tored		
Collaborative Partners	None												
R&D Providers	Sigma7												



Project Title	IFI 1007 – Outram Faul	t Level Monitor									
Description of project	The aim of this proje successfully measure f reliability. The develop where there is uncertagroups on the network	ault level on a disped instruments valued in fault level	tribution r vill be de <sub>l</sub>	network wit ployed in a	h repeatabilit t various loca	y and ations					
Expenditure for financial year	Internal £28,720 External £4,663 Total £33,384	Expenditure in (IFI) financial ye		Internal External <b>Total</b>	£1,849 £99,235 <b>£101,08</b>						
Project Cost	£121,196	F121,196 Projected 2012/13 costs for SPEN Internal £7,50 External £0 Total £7,50									
Technological area and / or issue addressed by project	assessment to exten downstream fault level	t is proposed that the instrument could provide a viable alternative for fault levents is seen to extensive modelling or at locations where upstream and downstream fault level can vary drastically over a period of time making traditional fault level analysis complex.									
Type(s) of innovation	Incremental	Significant		nological titution	Radical						
involved	Yes	No		No	No						
Expected Benefits of Project	<ul> <li>The release of net fault level.</li> <li>The deferment of perceived fault level</li> <li>Validation and imp</li> </ul>	f investment on helissues.	ealthy eq	uipment /	·						
Expected Timescale to adoption	<2 Years	Duration of beneather			10 Years						
		<del>                                     </del>		ent (Start – C							
Probability of Success	75%	1 2 3	4	5 6	7 8	9					
Project NPV	(Present Benefits x Pro Costs	bability of Success	– Present	£188,	.953						
Project Progress March 2012	<ul> <li>Outram Researched single phase fault le monitor platform.</li> <li>Subsequently a 3-ph additional requirements.</li> <li>SPEN are currently algorithm and firmwork is capable of produnetwork models.</li> <li>As of March thanks deployed the firmwork and underst</li> </ul>	evel monitor (FLM nase version has beents / features trialling x6 FLM uare and assess the late from site are versing results that a set to the variety of the late has been significant.	) based of een developments on the nstrumentry encourage re close to for locations ficantly up	on the PM7 oped by Ou d by SPEN ne network ts capabilitie aging and in o those ge s where the dated to ta	rooo power quitram incorpool based on to refine the es. dicate that the nerated by true FLMs have the account or	rating DNO FELM es FLM custed been					



Potential for achieving expected benefits	As of March the FLM is showing a high degree of promise and SPEN has confidence that the device will deliver accurate measurements. The initial results obtained have consistently been within 10% of the fault level produced from modelling packages.
Collaborative Partners	Outram Research Ltd
R&D Providers	Outram Research Ltd



Project Title	IFI 1101 – EPRI											
Description of project	SPEN has taken out morder to gain technical project will employ membership of EPRI pand expertise coverin Control which featur information in other amanagement.	al guida techno provide g HVDO e in th	ance an ologies s acces C, Series ne 2020	d expe that I s to a s Comp D prop	ertise to nave no wide rai pensatio osals. E	suppot year nge o n and PRI p	ort the t been f techr d Wide provide	2020 used iical do Area I s a w	Project in GE ocumen Monitor ide ran	This and tation ing & ge of		
Expenditure for financial year	Internal £11,465 External £97,931 Total £109,396	xternal £97,931 Expenditure in previous (IFI) financial years										
Project Cost	£360k for 3 year participation	I EXTERNAL ETZU.UUU										
Technological area and / or issue addressed by project	SPEN is one of the prand Climate Change (the 2020 vision for the transmission system of Scotland in excess of HVDC link between Some operational by 20 from Scotland to Englished Eliver the 2020 vision Involvement with EPR to the HVDC link development with EPR to the HVDC link development with EPR and Climb in the HVDC link development with EPR and Climb in the HVDC link development with EPR and Climb in the HVDC link development with EPR and Climb in the HVDC link development with EPR and Climb in the HVDC link development with EPR and Climb in the HVDC link development with EPR and Climb in the HVDC link development with EPR and Climb in the HVDC link development with EPR and Climb in the HVDC link development with EPR and Climb in the HVDC link development with EPR and Climb in the HVDC link development with EPR and Climb in the EPR an	DECC) e trans m in th 10GW ottishP 16 to f and. Th	Electric smission ne UK to by 202 ower a acilitate is is the	ity Net o facilit O. An o nd Nat e the fi e first o	tworks Sork. This ate the essential ional Grand of the formant of the following the fo	Strates wor delived de	gy Gro k has s ery of r verable is prop xpected oosed D	up (EN et the enewa of thi osed fo I renev OC links	footpri ble ene s work or this l wable e	ork on nt for rgy in is the ink to nergy UK to		
Type(s) of innovation	Incremental	Sig	gnifican	t		nolog stituti			Radical			
involved	Yes		Yes			Yes			Yes			
Expected Benefits of Project	<ul> <li>EPRI membership technologies and monitoring, contr</li> <li>SPEN individually assessment of pocompanies.</li> <li>As well as the Hyconsiderable beneminimisation and</li> </ul>	applica olling a or join ssible d /DC mo	ation of nd oper tly with esigns a odule, t SPEN, su	these rating b Nation and sol here a	technol HVDC lin nalGrid, utions p re many	ogies ks. can u rovide	in the Itilise E ed inte	areas PRI exproper exercites the second exercites are second exercites the second exercites t	of designeration of designeration designeration of the designeration of	in the ternal		
Expected Timescale to adoption	<2 Years	Dura achie	tion of eved	benefit	once			10 Yea	ars			
	TRL Development (Start – Current)											
Probability of Success	75%	1	2	3	4	5	6	7	8	9		
Project NPV	(Present Benefits x Pr Costs	obabilit	ty of Su	ccess) -	– Presen	it	£537,	245		l		
Project Progress March 2012	HVDC Technology Surveillance and Reference Guidelines											



	<ul> <li>Contracts are being placed to work on Reference Book chapters.         HVDC Reference Book will be published with all 24 chapters at the end of 2012.</li> <li>Applications of HVDC Technology and New Developments</li> <li>Contracts are being placed to work on AC vs DC Wizard software and</li> </ul>
	DC cable technology assessment.
	Integrating HVDC in an AC Grid
	<ul> <li>This project is coordinated with a supplemental project on the same topic in which application studies are conducted for the GB network for National Grid and ScottishPower</li> </ul>
	HVDC System Performance and Component Testing
	Full scale live line work tests have started at the Lenox laboratory
	<ul> <li>The HVDC insulator dimensioning guide is to be updated for 2012.</li> </ul>
	<ul> <li>A survey is being formulated to determine the performance of utility HVDC insulators</li> </ul>
	All deliverables are on schedule
	Electrical Effects of HVDC
	<ul> <li>Work on the electrical effects software has begun</li> </ul>
	<ul> <li>Plans are underway for experiments to be performed at the high voltage laboratory in Lenox.</li> </ul>
Potential for achieving expected benefits	Work has started on the collaborative project 'Integrating HVDC in an AC Grid'.
Collaborative Partners	NGC ( Integrating HVDC in an AC Grid)
R&D Providers	EPRI



Project Title	IFI 1102 – Energy Stor	age Pro	oject										
	The aim of this project grids.	is to ii	nvestiga	ite the	role of e	energy stora	ge syst	ems in	smart				
Description of project	The need to investigat governmental level. T (PRASEG) inquiry into storage as a 'possi generation' and high development' and 'cle Low Carbon Transition of key elements of a U	he Parl 'Rene ble so nlights ear poli n Plan (	liament wables lution the no tical an HM Go	ary Re and the for a eed food d regu	newable he grid: ddressing or 'Long latory sig	and Sustain access and g variable - term, fur gnals'(PRASE	nable E manag renew ther r EG, 201	Energy (gement' yable e esearch	Group cites nergy and he UK				
	Internal £14,272					Internal	f	<u> </u>					
Expenditure for financial	External £186		enditur financi			External	f	<u> 0</u>					
year	Total £14,457	otal £14,457 (IFI) financial years Total £0											
		Internal £10,000											
Project Cost	f326 000 Projected 2012/13 costs External £15.000												
		for SPEN Total <b>£25,000</b>											
Technological area and / or issue addressed by project	<ul> <li>Consideration of systems.</li> <li>Determine appropriate appr</li></ul>	most appriate of effects ent and ue throughlist gulator	approp peratin of ope d future ough en	g strat rating value ergy m	egies for strategie of oper narket ar	capacities energy stores on the aga ating an end bitrage. he ownershi	for en age sys geing c	ergy st stems. of the e	energy				
Type(s) of innovation	Incremental	Sig	nifican			nological titution		Radical					
involved	Yes		Yes			Yes		No					
Expected Benefits of Project	<ul> <li>Produce learning outcomes and decision support information which can be disseminated within the DNO community which will enable the cost effective and beneficial adoption of energy storage systems.</li> </ul>												
Expected Timescale to adoption	3 Years	Durat achie	tion of l ved	enefit	once		20 Yea	ars					
				TRL De	velopme	ent (Start – C	urrent	)					
Probability of Success	50%	1	2	3	4	5 6	7	8	9				
Project NPV	(Present Benefits x Probability of Success) – Present Costs  Not known at this stage												



Project Progress March 2012	Good work has been carried out in identifying relevant network models that can be used to mimic the effects of storage. These networks range from rural networks with historical voltage issues to urban networks with high percentage of embedded generation.
Potential for achieving expected benefits	It is hoped that the eventual output of the project will help Scottish Power plan strategically how and where the optimum use of Energy Storage should be.
Collaborative Partners	Electricity North West
R&D Providers	Durham University



Project Title	IFI 1103 – PD Monitorir	ng in Su	pergri	d Trans	sformers					
Description of project	The aim of this project 275KV / 33KV transforr DMS Ltd. After a period the accuracy of the mod	ner usir d of tes	ng a PC ting th	moni e tran	toring sy sformer	stem will b	suppli e insp	ied and ected t	d instal	led by
	Internal £8,750			_	_	Inte	ernal	f	20	
Expenditure for financial	External £76,421		enditur financi		ernal	f				
year	Total £85,170	(111)	IIIIaiic	ai yea	13	Tot	al	f		
				/ .	_	Inte	ernal	f	7,500	
Project Cost	£184,000	-	ected 2 SPEN	2012/1	.3 costs	Ext	ernal	f	85,000	)
		101 3	OF LIN			Tot	al	f	92,500	)
Technological area and / or issue addressed by project	The issue addressed by a supergrid transformer	-	-					_		alth of
Type(s) of innovation	Incremental	Sig	nifican	t	Techi subs	nolog tituti			Radica	ıl
involved	Yes		No			No			No	
Expected Benefits of Project	<ul> <li>Detection and mean continuous health of the continuous hea</li></ul>	checks of elopme rmer to	on tran ent in ank an	sform conju d the	er condit nction v interna	ion. vith con	Stratho struction	clyde l on and	Jnivers d then	sity to using
Expected Timescale to adoption	<2 Years	Durat achie	ion of ved	benefi	t once			10 Yea	ars	
			-	ΓRL De	velopme	nt (S	tart – C	Current	:)	
Probability of Success	50%	1	2	3	4	5	6	7	8	9
						ı	L			
Project NPV	(Present Benefits x Pro Costs	bability	of Suc	cess) –	- Present		£28,9	05		
Project Progress March 2012	-	All partial discharge monitoring equipment has now been installed. Work is now beginning to pull the data into a 3D model								
Potential for achieving expected benefits	This project is on target	to deli	ver the	benef	its.					
Collaborative Partners	None									
R&D Providers	University of Strathclyd	e								



Project Title	IFI 1107 –	Cable Identi	fication	Devic	es						
Description of project	either live and fall in DC is used identificat	Thas produce or dead circonsignal strend there is no cion which control of the develon te.	cuits. Id ngth alco curren other c	entifications the induction the induction the induction the inductions the induction t	ation is cable I ction in can su	via a vis ength c adjace uffer fro	sual di lue to nt cab om. T	splay v the lay les thu his pro	which s yup of is avoi oject v	shows the cording inconstill be	res. As correct a trial
Expenditure for financial year	Internal External <b>Total</b>	£9,703 £186 <b>£9,889</b>			e in pro			ernal ernal al		£0 £0 <b>£0</b>	
Project Cost	£4	Projected 2012/13 costs for SPEN Internal £7,500 External £25,000 Total £32,500									
Technological area and / or issue addressed by project	1	r there are a s device has								e is ope	ned in
Type(s) of innovation involved	Incren	nental	Sig	nifican	t		nolog stituti			Radica	I
ilivolved	Ye	es		No			Yes			No	
Expected Benefits of Project	circui  The I locati  Unne	cable detect ts and no cu requirement on is avoided cessary cust number of op ted.	rrent is to ex d. omer ir	induce cavate nterrup	d in ad an LV tions ai	jacent o cable e avoid	to the	s. le nea	rest k	nown s	ervice
Expected Timescale to adoption	<2`	Years	Durat achie		benefit	once			10 Ye	ars	
					TRL De	velopm	ent (S	tart – C	Curren	t)	
Probability of Success	9	0%	1	2	3	4	5	6	7	8	9
Project NPV	(Present Costs	Benefits x Pr	obabilit	ty of Su	ccess) ·	– Prese	nt	£1,12	3,305		
Project Progress March 2012		order was equent trial.	•	for fiv	e SEBA	A KMT	cable	identi	ficatio	n devic	es for
Potential for achieving expected benefits	_	that the to								-	-
Collaborative Partners	None										
R&D Providers	SEBA KMT	-									



Project Title	IFI 1108 –ESRI Powerf	actory											
Description of project	ScottishPower uses and by Esri UK known as F database. The system geographic basis. Sconetwork modelling and simulate electrical load Currently in the Scotti will take considerable the design and analysis an interface between modelling of the 11kV	GIS. The is used ottish Pend ana ading a shead amour is of the ESRI a	is hold: to creatower a lysis. The nd size er area nt of tin and Po	s elections electronical electr	rical pland maintal maintal place DigSILE of enable to mee are no regenerate ork. The	nt and in elections ENT Pes Scoot of give bbust in such projections	circui ctrical owerFa ettishPo en busi 11kV sy system ct will	t data i system actory ower to iness re ystem rode attemp	n an 'A model for eled models models Is to as ot to de	rcFM' s on a ctrical el and nents. and it sist in			
Expenditure for financial year	Internal £8,822 External £186	ternal £186 Expenditure in previous (IFI) financial years											
year	Total £9,007	otal £9,007 (IFI) financial years Total £0											
Project Cost	£98,000	£98,000 Projected 2012/13 costs for SPEN Internal £11,000 External £78,000 Total £89,000											
Technological area and / or issue addressed by project	the ESRI system with I network models of the design engineers with the design process and time consuming and process.	The aim is to develop a demonstrator project to proof the concept of interfacing the ESRI system with PowerFactory hence enabling the business to quickly develow network models of the 11kV system and possibly LV system. This will provid design engineers with up to date network models that can be utilised and enhance the design process and solutions evaluation. Generating 11kV models is laborious time consuming and prone to errors. This project will prove the concept of using GIS information to develop up to date electrical models.											
Type(s) of innovation involved	Incremental	Sig	gnifican	t		nologi			Radica				
	No		No			Yes			No				
Expected Benefits of Project	<ul> <li>To provide mecha</li> <li>Streamline existir 11kV network.</li> <li>To quickly run 'wh</li> </ul>	ng busii	ness pr	ocesse	s for the	e desi	gn and	conne		-			
Expected Timescale to adoption	<2 Years	Dura achie	tion of	benefit	once			10 Yea	ırs				
				TRL De	velopm	ent (Si	tart – C	Current	)				
Probability of Success	50%	1	2	3	4	5	6	7	8	9			
Project NPV	(Present Benefits x Pr Costs	obabili	ty of Su	ccess)	– Preser	nt	£1,60	8	<u> </u>	<u> </u>			
Project Progress March 2012	Project meetings with the project concluding		_	Silent a	ire due t	o tak	e place	during	g March	n with			
Potential for achieving expected benefits	There is hope that this project can build on the back of the distance to fault work carried out previously.												
Collaborative Partners  R&D Providers		None  ESPLUK and DigSHENT											
VAD LIONIGEI?	ESRI UK and DIgSILENT												



Project Title	IFI 1201 –Lynx Kelvat	ek LV S	witch								
Description of project	The 'Y' type network managed/switched duto be disconnected in isolationg. It is then root that any stage in the closing 11kV breake electromechanical de	uring 11 n order econne ne proc ers sim	LkV faul that th ected af ess does ultaneo	t isolatere with ter the snot outletone	ion and II be no 11kV r verload t each	restorestorestorestore	ration. feeds of tion. C I netwo of the	The LV onto th are has ork This fault.	netwo e fault s to be s may ir Lynx	rk has while taken nvolve	
Expenditure for financial year	Internal         £8,750           External         £186           Total         £8,935	ternal £186 Expenditure in previous (IFI) financial years External £0  Total £0									
Project Cost	£303,000	£303,000 Projected 2012/13 costs for SPEN Internal £15,000 External £120,000 Total £135,000									
Technological area and / or issue addressed by project	sectionalised as on a closing depending on	his project will develop a system that will allow the 11kV network to be ectionalised as on a radial system with the LV network automatically opening and losing depending on the 11kV status thus allowing engineers to focus solely on solation/restoration. This in turn will improve CML performance.								g and	
Type(s) of innovation	Incremental	Incremental Significant Technological substitution Radical									
involved	Yes		No			No			No		
Expected Benefits of Project	<ul><li>Improved CML pe</li><li>Established safeg of LV cables.</li></ul>			ent bad	k feedii	ng of I	HV cab	les and	l overlo	pading	
Expected Timescale to adoption	<2 Years	Dura achie	tion of l	oenefit	once			15 Yea	ars		
			1	TRL De	velopm	ent (S	tart – C	urrent	)	1	
Probability of Success	50%	1	2	3	4	5	6	7	8	9	
Project NPV	(Present Benefits x Pr Costs	obabili	ty of Su	ccess)	– Presei	nt	£107k	<u> </u>			
Project Progress March 2012	Currently under nego	tiation									
Potential for achieving expected benefits	It is expected that this	It is expected that this project will achieve its aim.									
Collaborative Partners	None										
R&D Providers	Kelvatek										



Project Title	IFI 1202 – Nanod	dielectr	ics								
Description of project	The aim of this processing of na and process rule materials.	nodiele	ectric i	materia	ıls in o	rder to	develo	p a set	t of ma	terials (	design
	Internal £8,7	750					Inte	ernal	f	<u> </u>	
Expenditure for financial year	External £18	86	Expenditure in previous (IFI) financial years  External £0  Total £0								
yeai	Total £8,9	935	(111)	IIIIaiici	ai yea	13	Tot	al	£0		
							Inte	ernal	f	7,500	
Project Cost	£104,980			ected 2 SPEN	2012/1	.3 costs	Ext	ernal	f	30,429	)
			101 3	DELIN			Tot	al	4	37,929	)
Technological area and / or issue addressed by project	will feed into HV with significant	ne understanding gained by this project and the materials design rules developed ill feed into HV equipment design to achieve new high performance equipment ith significantly improved voltage and power ratings and potentially much naller size for the same rating.									
Type(s) of innovation	Incremental		Sig	nifican	t		nnolog stituti			Radica	ĺ
involved	Yes			Yes			Yes			Yes	
Expected Benefits of Project	<ul> <li>Higher powe</li> <li>Longer insul</li> <li>Enhanced flee</li> <li>Greater resingular systems continue</li> <li>Lower capital</li> <li>Higher retain</li> </ul>	lation li exibility stance itaining al costs	fetime in ne to pov HVD( for ci	e and ir twork of wer ele C techn vil worl	nsulation operat ctronio ologie: ks.	on more ion. cs syster s.	tolera	int to d	overloa		
Expected Timescale to adoption	<3 Years		Durat achie	tion of ved	benefi	t once			10 Yea	ars	
					TRL D	evelopm	ent (S	tart – (	Current	:)	
Probability of Success	35%		1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefit Costs	ts x Pro	babilit	y of Su	ccess)	– Prese	nt	Not	known	at this	stage
Project Progress March 2012	Collaboration ag	Collaboration agreements are awaiting to be signed with kickoff expected on the									
Potential for achieving expected benefits	Not known at this stage										
Collaborative Partners	NGC, SSE										
R&D Providers	GnoSys UK, Univ National Physica	-		thampt	on and	d Areva	Resear	ch & T	echnol	ogy Cer	ntre,



Project Title	IFI 1203 – Psymetrix A	ACAM P	hase 1							
Description of project	The objective of thi Management (ANM) (ACAM). Then initiate facilitating the conne (Phase 2).	approa e its d	ich kno evelopr	wn as nent i	Angle onto an o	Const opera	raint A	ctive I scheme	Manage e capal	ement ble of
Expenditure for financial year	Internal	- I	enditur financi	-			ernal ernal <b>al</b>	£	0 0 0	
Project Cost	£320,655	Projected 2012/13 costs for SPEN  Internal £20,000  External £160,000  Total £180,000								0
Technological area and / or issue addressed by project	T =	ne project will contribute to the UK environmental targets by enabling a greater enetration of renewable generation on to the electrical network.								
Type(s) of innovation	Incremental	Sig	gnifican	t		nolog			Radica	
involved	Yes		No			No			No	
Expected Benefits of Project	<ul> <li>introduce</li> <li>To prove the comeasurements</li> <li>To identify the op</li> <li>To gain the necesscheme</li> </ul>	eration	ıal requ	iremer	nts of an	ACAN	1 scher	ne		
Expected Timescale to adoption	2 Years	Dura achie	tion of l eved	oenefit	once			10 Yea	rs	
			_	TRL De	evelopme	ent (S	tart – C	urrent	)	
Probability of Success	35%	1	2	3	4	5	6	7	8	9
Project NPV	(Present Benefits x Pr Costs	obabili	ty of Su	ccess)	– Presen	it		£187	,974	
Project Progress March 2012	<ul><li>Contract with Ps</li><li>PMU order place</li></ul>	Contract with Psymetrix placed.								
Potential for achieving expected benefits	As this is a proof of concept trial and yet to start in earnest, at this stage, based on academic feasibility studies this project has good potential to deliver its benefits. Once the equipment is installed later on in the year the ability to realise expected benefits will be better understood.									
Collaborative Partners	Psymetrix	Psymetrix								
R&D Providers	Psymetrix									



Project Title	IFI 1204 – LV Jumpers with Integral CB												
Description of project	The development of a set of a prototype Low Voltage (LV) jumper set to be used in conjunction with a suitably graded portable LV circuit breaker. The full arrangement to be used to energise LV circuits from adjacent live circuits during LV busbar outages, hence reducing customer outages and mobile generator costs. Assuming the prototype proves successful the project will be extended to include evaluation of several units on the network.												
- III 6 6 I	Internal	E	Expenditure in				Internal £0						
Expenditure for financial year	External £186			previous (IFI) financial				External £0					
yeur	Total	ye	years				otal £0						
			Projected 2012/13				ernal						
Project Cost	£	:60k		rojected osts for		./13	Ext	ernal					
					31 211		Tot	Total <b>£40,000</b>					
Technological area and / or issue addressed by project		The prototype arrangement would provide a technical solution to reduce customer outages and mobile generator costs / emissions.											
Type(s) of innovation involved	Increm	Sig	Significant			Technological substitution			Radical				
	Ye		No I			No		No					
Expected Benefits of Project	<ul> <li>Reduction in the mobile generation emissions and costs associated with LV busbar outages.</li> <li>Additional operational applications and benefits derived from field trials and business exposure to the device.</li> </ul>												
Expected Timescale to adoption	<2 Y	ears	Duration of benefit once achieved 10 Years										
			TRL Developm					nent (Start – Current)					
Probability of Success	75%		1	2	3	4	5	6	7	8	9		
Project NPV	(Present Benefits x Probability of Success) – Present Costs												
	<ul> <li>The initial prototype arrangement of flexible LV jumpers and portable circuit breaker was manufactured by Ten47 and delivered to SPEN in early March.</li> <li>The prototype was installed on a dead LV busbar at the SPEN training complex shortly afterwards.</li> <li>The basic installation tests provided confidence that the arrangement was a feasible solution and was of suitable construction for a substation environment.</li> <li>Several design improvements were identified during the testing and the prototype has been subsequently taken back by Ten47 to implement them.</li> <li>Version 2 to be trialled in May / June 2012.</li> </ul>												
Project Progress March 2012	The process of t	ker was mar prototype was plex shortly a pasic installable solution conment. Fal design in ptype has be con 2 to be t	type and typ	rrangen ured by nstalled vards. tests produced was vements bsequer in May	nent o Ten47 on a ovided of si s were ntly tal / June	f flexible and de dead confide uitable de identi ken back	e LV diverse cons	jumpe d to Si usbar that th truction during en47 t	PEN in eat the ne arrai on for the te o imple	early Ma SPEN t ngemen a sub esting a	t was a ostation nd the nem.		
_	The property of the state	ker was mar prototype volex shortly so pasic installable solution conment. cal design in	type and a	rrangen ured by nstalled vards. dests prod d was vements bsequer in May itial prod operate	nent or Ten47 on a covided of so were ntly tal / June cototyptional f the	f flexible and de dead confide uitable e identi ken back 2012. e arran scenario compor	e LV bilivered LV bilivered consistence co	jumper d to Si usbar that th truction during en47 the ent ha is of a have	PEN in eat the at the arrange on for the ten implementations of the second of the seco	early Ma SPEN to ngement a sub esting a ement the onstrate ole design	t was a estation and the nem.		
2012  Potential for achieving	The property of the state	ser was man prototype values shortly a pasic installated solution conment. The design is portaged as be con 2 to be to be ded above to be being used on standard	type and a	rrangen ured by nstalled vards. dests prod d was vements bsequer in May itial prod operate	nent or Ten47 on a covided of so were ntly tal / June cototyptional f the	f flexible and de dead confide uitable e identi ken back 2012. e arran scenario compor	e LV bilivered LV bilivered consistence co	jumper d to Si usbar that th truction during en47 the ent ha is of a have	PEN in eat the at the arrange on for the ten implementations of the second of the seco	early Ma SPEN to ngement a sub esting a ement the onstrate ole design	t was a estation and the nem.		



Project Title	IFI 1209 - Substation Earth Integrity Monitoring System									
Description of project	This aim of this project is to develop a system for monitoring the removal/theft of earth straps from Transmission and Distribution substations or other installations									
Expenditure for financial year	Internal £7,418 External £186 Total £7,604		-	liture in is (IFI) financial	Interna Externa Total					
Project Cost	£189,34	£189,347		ed 2012/13 or SPEN	Interna Externa Total	•				
Technological area and / or issue addressed by project	The project will explore three separate work streams  1) Use of RFID technology using RFID tags bonded to earth straps that are monitored (pinged) by a monitoring unit on site to detect their presence.  2) To prove the concept of using SWR (Standing Wave Ratio) as used in radio/antenna optimisation to provide detection of real time "earth tamper" activity.  3) Develop the Cresatech Copper Theft Sensor (CuTS) protype unit for application at ScottishPower substations.									
Type(s) of innovation involved	Took Transfer	Project Be Ratin		Project Residua	al Risk	Overall Project Score				
	Tech Transfer	10		-1		11				
Expected Benefits of Project	There is no off the shelf product available for permanent installation in a substation which can detect the presence of adequate earthing and real time theft detection.									
Expected Timescale to adoption	1 year	Duratio	on of benefit once achieved	2	15 years					
Probability of Success	50%	Bene	eject NPV = (PV fits – PV Costs) x ability of Success	£71,378						
Potential for achieving expected benefits	Work streams 1 and 2 are at an early stage and, as commented on below, early results are not as good as expected. The potential for success is therefore inconclusive.									
Project Progress to March 12	The project only started shortly before the year end, so there is very little progress to report at this time, other than early experience of work streams 1 and 2 has not given encouraging results so far. Work stream 3 has yet to start.									
Collaborative Partners	Scottish Power									
R&D Providers	Nortech Online Ltd, Cresatech									



Project Title	IFI 1210 –Transmission SSR & Harmonics												
Description of project	SPT is currently undertaking two projects to improve the visibility of the transmission network in readiness for the 2020 reinforcement programme. One project looks to provide essential data on the network harmonics that are required to be Grid Code compliant and is now required to the design of HVDC filters. The second project is the monitoring of several generation sites in England and Scotland that have been identified as being at risk to Sub-Synchronous Resonance (SSR) as a result of the proposed Series Compensation schemes on the Anglo-Scottish border.												
Expenditure for financial year	Internal		_			Inte	ernal	£					
	External	-	enditur financi	-		Ext	ernal	£					
•	Total			,		Tot	al	£0					
				040/4		Inte	ernal	£12,500					
Project Cost	£14	_	Projected 2012/13 costs for SPEN				ernal	£	0				
							al	£	0				
Technological area and / or issue addressed by project	The aims of this project are to enhance both projects using advanced hardware / software solutions to: (1) Automatically accumulate process and analyse the harmonic data to create useful system harmonic information. (2) To advance the design of a network fault recorder to accommodate SSR detection as a standard feature in readiness of the Series Compensation being added to the network.												
Type(s) of innovation	Incremental		Sig	Significant			nnolog stituti		Radical				
involved	Ye		No			No	) No						
Expected Benefits of Project	<ul> <li>Production of automatic harmonic reports that would have otherwise required several man hours of effort each day to recreate.</li> <li>Both projects will decrease the risk to external parties connected to the transmission network. In particular SSR detection will prevent the mechanical failure of SSR susceptible turbines connected to the network.</li> <li>SPT will have increased awareness of the SSR phenomena and its detection in advance of series compensation. SPT will have greater visibility of the networks harmonic performance and have a greater ability to police it against the Grid Code, with increasing levels of low carbon technology connecting to the network.</li> </ul>									o the anical ion in f the gainst			
Expected Timescale to adoption	<2 Y	'ears		Duration of benefit once achieved					15 Years				
Probability of Success					TRL De	velopm	ent (S	ent (Start – Current)					
	75%		1	2	3	4	5	6	7	8	9		
Project NPV	(Present Benefits x Probability of Success) – Present Costs  To be determin						nined						
Project Progress March 2012	This project has just started, with the majority of costs being internal.												
Potential for achieving expected benefits	The potential of this project will be realised once equipment is installed in the field and we start to obtain results.												
Collaborative Partners	None QUALITROL & PI												
R&D Providers	LUALITKU	LQPI											